

CONCRETE COLLAR					
LOCATION			CU YD	REMARKS	
77+03.00		63.00'	RT	1.60	ALLEN RD (60" PIPE)
11+41.00		21.50'	RT	0.40	VAN WINKLE (15" PIPE)
16+70.70		29.00'	RT	0.60	VAN WINKLE (24" PIPE)
TOTAL			2.6	ROUND TO 3	

STORM SEWER REMOVAL 18"					
LOCATION			FOOT	REMARKS	
71+86.87	TO	72+70.03	LT	88.55	ALLEN RD
11+40.84	TO	11+48.08	LT	14.60	VAN WINKLE WAY
TOTAL			103.2	ROUND TO 104	

STORM SEWER REMOVAL 24"					
LOCATION			FOOT	REMARKS	
73+26.52	TO	73+49.70	LT	30.55	ALLEN RD
73+49.70	TO	73+95.01	LT	47.73	ALLEN RD
TOTAL			78.3	ROUND TO 79	

REMOVING MANHOLES					
LOCATION			EACH	REMARKS	
16+90.19		54.23'	LT	1	VAN WINKLE WAY
16+76.41		43.92'	RT	1	VAN WINKLE WAY
TOTAL			2	ROUND TO 2	

REMOVING INLETS					
LOCATION			EACH	REMARKS	
16+70.01		31.27'	LT	1	VAN WINKLE WAY
11+41.05		21.64'	RT	1	VAN WINKLE WAY
11+47.74		21.70'	RT	1	VAN WINKLE WAY
TOTAL			3	ROUND TO 3	

CLASS SI CONCRETE (OUTLET)					
LOCATION			CU YD	REMARKS	
56+55.21	TO	56+89.40	RT	3.07	ALLEN RD
60+15.40	TO	60+50.44	RT	3.07	ALLEN RD
97+10.40	TO	97+22.35	LT	1.20	ALLEN RD
97+63.30	TO	97+75.38	LT	1.20	ALLEN RD
115+80.00	TO	116+13.50	15' LT	3.07	ALTA LN
TOTAL			11.61	ROUND TO 12	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18					
LOCATION			FOOT	REMARKS	
119+25.69	TO	121+36.93		256.78	ALTA LN
119+26.97	TO	121+35.54		225.71	ALTA LN
42+04.20	TO	43+27.54		123.33	BROMPTON CT
TOTAL			605.8	ROUND TO 606	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24					
LOCATION			FOOT	REMARKS	
48+45.61	TO	50+95.85	LT	285.29	ALLEN RD
47+90.31	TO	56+45.93	RT	856.48	ALLEN RD
51+44.70	TO	51+89.07	LT	120.89	IL 6 NB RAMPS
52+26.11	TO	56+89.40	LT	531.82	ALLEN RD
60+15.40	TO	65+08.71	LT	542.04	ALLEN RD
60+15.40	TO	72+76.46	RT	1388.72	ALLEN RD
65+43.29	TO	65+85.12	LT	123.26	IL 6 SB RAMPS
66+24.72	TO	72+72.04	LT	813.75	ALLEN RD
73+18.12	TO	83+63.65	LT	1171.08	ALLEN RD
73+21.07	TO	85+82.32	RT	1337.77	ALLEN RD
86+18.50	TO	95+65.67	RT	967.93	ALLEN RD
86+91.02	TO	95+67.49	LT	876.91	ALLEN RD
114+33.49	TO	118+43.31	RT	569.24	ALTA LN
116+13.52	TO	118+26.70	LT	234.20	ALTA LN
TOTAL			9819.4	ROUND TO 9820	

COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (VARIABLE WIDTH GUTTER FLAG)					
LOCATION				FOOT	REMARKS
0+82.98	TO	0+97.28	LT	14.38	RAMP A
23+77.11	TO	23+93.16	LT	16.13	RAMP B
23+16.67	TO	23+35.78	LT	19.19	RAMP C
1+95.79	TO	2+11.91	LT	16.23	RAMP D
56+01.41	TO	56+32.91	RT	31.73	ALLEN RD
56+45.93	TO	56+89.40	RT	43.50	ALLEN RD
119+16.97	TO	119+26.97	RT	10.01	ALTA LN
119+15.69	TO	119+25.69	LT	10.01	ALTA LN
TOTAL			161.2	ROUND TO 162	

COMBINATION CONCRETE CURB AND GUTTER, TYPE M (MODIFIED)					
LOCATION				FOOT	REMARKS
56+45.93	TO	56+89.40	RT	43.50	ALLEN RD
TOTAL			43.5	ROUND TO 44	

CONCRETE MEDIAN, TYPE SB-6.12					
LOCATION				SQ FT	REMARKS
46+00.00	TO	51+31.29		3195.49	
51+92.28	TO	56+89.40		7358.22	
60+15.40	TO	60+49.71		205.51	
61+52.90	TO	65+18.42		2175.13	
66+02.21	TO	72+39.45		10042.70	
TOTAL			22977.1	ROUND TO 22978	

CONCRETE MEDIAN TRANSITION					
LOCATION				SQ FT	REMARKS
60+49.59	TO	60+59.71		60.00	
61+42.91	TO	61+53.02		60.00	
TOTAL			120.0	ROUND TO 120	

ISLAND PAVEMENT (8")					
LOCATION				SQ YD	REMARKS
51+15.80		36.7'	LT	48.68	
65+22.39		42.7'	LT	39.42	
66+30.52		41.6'	LT	31.89	
85+42.55		28.5'	LT	295.74	
TOTAL			415.7	ROUND TO 416	

STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS					
LOCATION				FOOT	REMARKS
116+62.24	TO	117+27.69	LT	62.5	NW QUAD ALTA LANE
TOTAL			62.5	ROUND TO 63	

TRAFFIC BARRIER TERMINAL, TYPE 6					
LOCATION				EACH	REMARKS
59+97.40	TO	60+43.05	LT	1	ALLEN RD. BRIDGE
TOTAL			1	ROUND TO 1	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT					
LOCATION				EACH	REMARKS
60+43.05	TO	60+93.04	LT	1	ALLEN RD. BRIDGE
TOTAL			1	ROUND TO 1	

TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED					
LOCATION				EACH	REMARKS
116+10.40	TO	116+62.24	LT	1	ALTA LN
117+27.69	TO	117+79.37	LT	1	ALTA LN
TOTAL			2	ROUND TO 2	

MAURER-STUTZ
ENGINEERS SURVEYORS

FILE NAME =	USER NAME = jdspliller	DESIGNED -	REVISED -
S:\237\2013\23713009\00\AllenRd\11\CADD	CADD Sheets\0468683-sht-schedule.dgn	DRAWN -	REVISED -
Default	PLOT SCALE = 20.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 1/31/2014 10:32:26 AM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

ALLEN ROAD IMPROVEMENTS
SCHEDULE OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.U. RE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6584	105: (72-7HB)BY	PEORIA	487	49
6585			CONTRACT NO. 68683	
ILLINOIS FED. AID PROJECT				