TEMPORARY PAVEMENT MARKINGS

STATION TO STATION	WHITE SOLID 4"	YELLOW SOLID 4"	WHITE SOLID 8"	WHITE DOTTED 8"	WHITE SOLID 12"	YELLOW SOLID 12"	WHITE SOLID 24"	WHITE SKIP-DASH 6"	LETTERS AND SYMBOLS	TEMP. RAISED REFLECTIVE PAVEMENT MARKERS 2-WAY AMBER
	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	(40' SPACING) EACH
STAGE I										
ALLEN RD. STA. 33+00 TO 85+50	7537	9997	308	609		497	112		78	4326
NB RAMPS	661	316					28			
SB RAMPS	464	532					29			
VAN WINKLE WAY (WEST)	586	684					12			
VAN WINKLE WAY (EAST)	519	494					12			
ALTA(WEST)										
ALTA (EAST)										
STAGE I TOTAL	**9767**	**12023**	**308**	**203**	**0**	**497**	**193**	**0**	**78**	**108**
STAGE IA										
ALLEN RD. STA. 43+50 TO 85+50	301	726	235				47		47	
NB RAMPS										
SB RAMPS	253									
VAN WINKLE WAY (WEST)	596	672					27			
VAN WINKLE WAY (EAST)	583	466					12			
ALTA(WEST)										
ALTA (EAST)										
STAGE IA TOTAL	**1733**	**1864**	**235**	**0**	**0**	**0**	**86**	**0**	**47**	**0**
STAGE IB										
ALLEN RD. STA. 43+50 TO 85+50	65	618	181				62		31	
NB RAMPS										
SB RAMPS	365		371				32			
VAN WINKLE WAY (WEST)	451	508					13			
VAN WINKLE WAY (EAST)	352	670					12			
ALTA(WEST)										
ALTA (EAST)										
STAGE IB TOTAL	**1233**	**1796**	**552**	**0**	**0**	**0**	**119**	**0**	**31**	**0**
WINTER										
ALLEN RD. STA. 43+50 TO 97+60	6237	7645	1792	532			180	1738	265	
NB RAMPS			918		128				140	
SB RAMPS	105		677		79		49		140	
VAN WINKLE WAY (WEST)		622	150		180		40		31	
VAN WINKLE WAY (EAST)			775		113		34		47	
ALTA(WEST)										
ALTA (EAST)										
WINTER TOTAL	**6342**	**8267**	**4312**	**177**	**500**	**0**	**303**	**435**	**623**	**0**
STAGE II										
ALLEN RD. STA. 43+50 TO 85+50	6489	10359	315	361		782	97		125	4602
NB RAMPS			883		216		62			
SB RAMPS			839		209		48			
SB IL 6 Sta. 911+00 to 930+00	1900	1900								
NB IL 6 Sta. 928+00 to 947+00	1900	1900								
VAN WINKLE WAY (WEST)	564		283				26			
VAN WINKLE WAY (EAST)	569		269				12			
ALTA(WEST)										
ALTA (EAST)										
STAGE II TOTAL	**11422**	**14159**	**2589**	**120**	**425**	**782**	**245**	**0**	**125**	**115**

CONTINUED ON NEXT SHEET

CONTINUED FROM PREVIOUS SHEET

TEMPORARY PAVEMENT MARKINGS

STATION TO STATION	WHITE SOLID 4"	YELLOW SOLID 4"	WHITE SOLID 8"	WHITE DOTTED 8"	WHITE SOLID 12"	YELLOW SOLID 12"	WHITE SOLID 24"	WHITE SKIP-DASH 6"	LETTERS AND SYMBOLS	TEMP. RAISED REFLECTIVE PAVEMENT MARKERS 2-WAY AMBER
	FT	FT	FT	FT	FT	FT	FT	FT	SQ FT	(40' SPACING) EACH
STAGE IIA										
ALLEN RD. STA. 43+50 TO 85+50										
NB RAMPS										
SB RAMPS										
VAN WINKLE WAY (WEST)	579	561					12			
VAN WINKLE WAY (EAST)	854	379					23			
ALTA(WEST)										
ALTA (EAST)										
STAGE IIA TOTAL	**1433**	**940**	**0**	**0**	**0**	**0**	**35**	**0**	**0**	**0**
STAGE IIB										
ALLEN RD. STA. 43+50 TO 85+50	1361	2679	159	220		133	31		250	
NB RAMPS									140	
SB RAMPS									94	
VAN WINKLE WAY (WEST)	353	368					12		31	
VAN WINKLE WAY (EAST)	491	769					21		47	
ALTA(WEST)										
ALTA (EAST)										
STAGE IIB TOTAL	**2205**	**3816**	**159**	**73**	**0**	**133**	**64**	**0**	**562**	**0**
STAGE III										
ALLEN RD. STA. 43+50 TO 97+60	2067	10284	1356	1234			185			1018
NB RAMPS										
SB RAMPS			272							
SB IL 6 Sta. 911+00 to 930+00	1900	1900								
NB IL 6 Sta. 928+00 to 947+00	1900	1900								
VAN WINKLE WAY (WEST)		375	188				40			
VAN WINKLE WAY (EAST)		544	544		74		36			
ALTA(WEST)										
ALTA (EAST)										
STAGE III TOTAL	**5867**	**15003**	**2360**	**411**	**74**	**0**	**261**	**0**	**0**	**25**
STAGE IIIA										
ALLEN RD. STA. 43+50 TO 97+60		3510	902	971			33			
NB RAMPS										
SB RAMPS	184		803				52			
VAN WINKLE WAY (WEST)										
VAN WINKLE WAY (EAST)										
ALTA(WEST)										
ALTA (EAST)										
STAGE IIIA TOTAL	**184**	**3510**	**1705**	**324**	**0**	**0**	**85**	**0**	**0**	**0**
GRAND TOTAL	**101564**		**13529**		**2411**		**1391**	**435**	**1466**	**249**