

TREE SCHEDULE							
LOCATION	TREE, CERCIS CANADENSIS (REDBUD), CONTAINER GROWN, 5-GALLON	TREE, TAXODIUM DISTICHUM (BALD CYPRESS), CONTAINER GROWN, 5-GALLON	TREE, TILIA AMERICANA (AMERICAN LINDEN), 1-1/4" CALIPER, CONTAINER GROWN	TREE, PLATANUS OCCIDENTALIS (SYCAMORE), CONTAINER GROWN, 5-GALLON	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), CONTAINER GROWN, 5-GALLON	EVERGREEN, PICEA PUNGENS (COLORADO SPRUCE), 3' HEIGHT, CONTAINER	TREE, CELTIS OCCIDENTALIS (COMMON HACKBERRY), 1-1/4" CALIPER, CONTAINER GROWN
	EACH	EACH	EACH	EACH	EACH	EACH	EACH
ALLEN RD.							
LT. and RT. Sta. 80+70 to 95+50	65	65	65	65	65	65	65
ALTA LN.							
LT. and RT. Sta. 119+00 to 121+20	15	15	15	15	15	15	15
TOTAL	80	80	80	80	80	80	80

NOTE: The Engineer shall determine the specific locations for the trees within the limits provided.

REMOVE EXISTING SEPTIC TANK	
LOCATION	EACH
Sta. 82+50, 150' RT	1
Sta. 84+00, 100' RT	1
Sta. 89+50, 115' LT	1
TOTAL	3

LOCATION	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	TRAFFIC CONTROL SURVEILLANCE	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)
	EACH	EACH	L SUM	L SUM	L SUM	CAL DA	L SUM
IL 6	2	2	1	1	1		
JOBSITE						250	
JOBSITE, EXCEPT IL 6							1
TOTAL	2	2	1	1	1	250	1

SEALING ABANDONED WATERWELLS	
LOCATION	EACH
Sta. 84+25, 45' RT	1
TOTAL	1

LOCATIONS	PIPE CULVERTS, CLASS D, TYPE 1 (TEMPORARY), 12"	PIPE CULVERTS, CLASS D, TYPE 1 (TEMPORARY), 15"	PIPE CULVERTS, CLASS D, TYPE 2 (TEMPORARY), 18"	PIPE CULVERTS, CLASS D, TYPE 1 (TEMPORARY), 24"
	FT	FT	FT	FT
PRE-STAGE				
LT. Sta. 78+94 to 80+50		156		
STAGE I				
RT. Sta. 93+93 to 94+96	105			
RT. Sta. 95+00				65
RT. Sta. 95+50			22	
TOTAL	105	156	22	65

CHANGEABLE MESSAGE SIGN		
LOCATION	CAL MO	NOTES
JOBSITE	12	2 signs at 6 months
TOTAL	12	each