	T ,			SIGN PANEL	SIGN PANEL	SIGN PANEL	TELES STL SIN		STEEL	SIGN POST S	SUPPORT - E	REAK AWA	AY		CONC	
ROADWAY	LOCATION	SIGN CODE		TYPEI	TYPE 2	TYPE 3		STEEL POST		MAIN POST LENGTH			WEIGHT	STR STL	FOUNDATION	
			MESSAGE OR DESCRIPTION	,	,			SIZE	LENGTH	L1 L2		L3	(POUND)			COMMENT
				(SQ FT)	(SQ FT)	(SQ FT)	(FOOT)		(FOOT)	(FOOT)	(FOOT)	(FOOT)	PER FOOT	(POUND)	(CU YD)	
ALLEN ROAD	STA 38+45, 53' RT	M1-I100	ILLINOIS 6	9			17									
		M2-1	JUNCTION	2.19												MOUNT WITH M1-I100
		M6-3	THRU ARROW	2.19												MOUNT WITH M1-I100
ALLEN ROAD	STA 45+32, 55' RT (BK TO BK)	R1-1	STOP	2.25			14.50									ON MULTI-USE PATH
		R5-3	NO MOTOR VEHICLES	4.00												MOUNT WITH R1-1
ALLEN ROAD	STA 46+90, 60' RT	N/A	CUSTOM GUIDE SIGN			120.00		W10X22	3.0	20.5	20.1		22	1025.2	2.4	
ALLEN ROAD	STA 49+40, RT	N/A	CUSTOM GUIDE SIGN			152.25										MOUNT ON EXISTING SIGN TRUSS
ALLEN ROAD	STA 49+40, RT	N/A	CUSTOM GUIDE SIGN			126.00										MOUNT ON EXISTING SIGN TRUSS
	STA 54+26, 75.5' LT	N/A	CUSTOM GUIDE SIGN			96.00		W12X26	3.0	17.5	18.3		26	1086.8	2.8	
ALLEN ROAD	STA 54+63, 40.5' RT		ILLINOIS 6	9.00			18				ļ					
		M3-1	SOUTH	4.50												MOUNT WITH M1-I100
		M5-1	ADVANCE TURN ARROW (LEFT)	2.19												MOUNT WITH M1-I100
ALLEN ROAD	STA 60+60, 40.8' LT	M1-I100	ILLINOIS 6	9.00			18									
		M3-1	NORTH	4.50												
		M5-1	ADVANCE TURN ARROW (RIGHT)	2.19						1	ļ					
ALLEN ROAD	,	N/A	CUSTOM GUIDE SIGN			132.00				1						MOUNT ON NEW CANTILEVER
	STA 68+29, 88' LT	N/A	CUSTOM GUIDE SIGN			188.50		W10X22	3.0	19.0	18.0		22	946.0	2.4	
	STA 71+29, 70.5' LT	N/A	CUSTOM GUIDE SIGN			120.00		W8X18	2.5	17.3	15.0		18	671.4	1.4	
	STA 928+50, RT	N/A	CUSTOM GUIDE SIGN			130.50				1						MOUNT ON BRIDGE
	STA 72+44, 71' RT	R1-1	STOP	2.25			10.50									ON MULTI-USE PATH
	STA 73+61, 50' RT	R1-1	STOP	2.25			10.50									ON MULTI-USE PATH
	STA 74+47, 40' RT	W9-2	RIGHT LANE MERGE	9.00			15									
ALLEN ROAD	STA 79+30, 35.5' LT		ILLINOIS 6	9.00			18									
		M2-1	JUNCTION	2.19												MOUNT WITH M1-I100
		M6-3	THRU ARROW	2.19												MOUNT WITH M1-I100
	STA 79+40, 37' RT		RIGHT LANE ENDS AHEAD	9.00			15									
	STA 19+70, 50.6' RT	N/A	CUSTOM GUIDE SIGN			65.00		W6X15	2.5	12.5	13.0		15	495.0	2.1	
	STA 80+33, 65' RT		ROCK ISLAND TRAIL WITH ARROW	5.69			10.6									3" LETTERS; WHITE ON BROWN; ON MULTI-USE PAT
	STA 80+74, 64' RT	R1-2	YIELD	2.00			11									ON MULTI-USE PATH
	STA 80+76, 60' RT		ROCK ISLAND TRAIL WITH ARROW	5.69			10.1									3" LETTERS; WHITE ON BROWN; ON MULTI-USE PAT
ALLEN ROAD	STA 82+00, 30' RT	D3-1	ALTA LN	5.00			14									
		M5-1	ARROW - LEFT	2.19												MOUNT WITH D3-1
ALLEN ROAD	STA 84+30, 158' RT (MOUNT BK TO BK ON 1 POST)	D1-1	ROCK ISLAND TRAIL WITH ARROW	5.69			10.5			ļ						3" LETTERS; WHITE ON BROWN; ON MULTI-USE PAT
		R1-2	YIELD	2.00												MOUNT WITH D1-1
	STA 84+65, 141 RT	R5-3	NO MOTOR VEHICLES	4.00			14.5									ON MULTI-USE PATH
ALLEN ROAD	STA 85+52, 44' RT (BK TO BK)		NO MOTOR VEHICLES	4.00			14									ON MULTI-USE PATH
		R1-1	STOP	2.25						<u> </u>						MOUNT WITH R5-3
	STA 86+40, 27' RT	R1-1	STOP	2.25			10.5			_						ON MULTI-USE PATH
	STA 87+46, 31' LT	W4-3	ADDED LANE	3.00			15									
ALLEN ROAD	STA 90+00, 24' LT	D3-1	ALTA LN	5.00			14									
		M6-2	ARROW - RIGHT	2.19						-						MOUNT WITH D3-1
ALTA LN	STA 114+69, 32' RT (TOP TO BTM)	M3-1	NORTH	2.00			14			-						WHITE ON GREEN
		D3-1	ALLEN RD	5.00						-						WHITE ON GREEN; MOUNT WITH M3-1
	OTA 444 00 000 DT (TOD TO TO)	M5-1	ARROW - LEFT	2.19				ļ		1						WHITE ON GREEN; MOUNT WITH M3-1
ALTA LN	STA 114+69, 32' RT (TOP TO BTM)	M3-3	SOUTH	2.00			14			1						WHITE ON GREEN
		D3-1	ALLEN RD	5.00						1	 					WHITE ON GREEN; MOUNT WITH M3-1
	074.447.00.741.07	M6-2	ARROW - RIGHT	2.19			45			1	ļ					WHITE ON GREEN; MOUNT WITH M3-1
	STA 117+66, 71' RT		ADDED LANE	3.00			15			1	-					
	STA 118+18, 27' RT		STOP	9.00			15			1						
	STA 119+10, 25' LT		STOP	9.00			15	 		1						OUL ETTERO MULTE ON DE COMO CONTUITO E E
	STA 120+06, 112' RT		ROCK ISLAND TRAIL WITH ARROW	5.69			10.1			1						3" LETTERS; WHITE ON BROWN; ON MULTI-USE PAT
	STA 121+05, 25' RT		STOP	9.00			15	ļ		1	-					
	STA 121+35, 50' LT		STOP	9.00			15			1	ļ					
ALTA LN	STA 121+75, 45' RT	R1-1	STOP	9.00			15			1	ļ					
										1						
			Totals	210		1,131	388.8							4224.4	11.1	

NOTE: ALL SIGNS SHOWN IN THE SIGN SCHEDULE WILL BE CONSTRUCTED AS PART OF THIS PROJECT. THE SIGN PLAN ONLY SHOWS SIGNS REQUIRED FOR THE ALLEN ROAD INTERCHANGE WITH IL 6. ADDITIONAL SIGNS NOT SHOWN ON THE PLANS SHALL BE CONSTRUCTED AT THE LOCATIONS SHOWN IN THE SCHEDULE.

FILE NAME =	USER NAME = aubreygs	DESIGNED -	REVISED -
S:\GEN\DRAFT\STD&PLNS\SQUAD3\Allen Rd\	inal Sheet Revisions\Revised Sheets.dgn	DRAWN -	REVISED -
	PLOT SCALE = 20.0000 '/ in.	CHECKED -	REVISED -
Default	PLOT DATE = 1/31/2014 1:48:09 PM	DATE -	REVISED -

STATE OF ILLINOIS	
DEPARTMENT OF TRANSPORTATION	

		010111		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.				
SIGNING SCHEDULE							105; (72-7HB)BY	PEORIA	487	64		
				6585		CONTRACT	NO. 6	8683				
SCALE:	SHEET	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT					