TEMPORARY PAVEMENT MARKING LEGEND

(1)	4'' SOLID (WHITE)	(6)	24'' SOLID (WHITE)
(2)	4'' SOLID (YELLOW)	(7)	4'' DOUBLE SOLID (YELLOW)
(3)	8'' SOLID (WHITE)	(8)	6'' SKIP DASH (WHITE)
(4)	12'' SOLID (WHITE)	(9)	8'' DOTTED (WHITE)
(5)	12'' SOLID (YELLOW)	(10)	LETTERS AND SYMBOLS (WHITE)

TEMPORARY RAISED REFLECTIVE PAVEMENT MARKERS LEGEND

1	ONE-WAY CRYSTAL MARKER
2	TWO-WAY AMBER MARKER

LEGEND

PROPOSED CONSTRUCTION

VERTICAL BARRICADES OR DRUMS

PROPOSED TEMPORARY PAVEMENT

N

MATCHLINE STA. 67+50

VAN WINKLE

STA. 67+72.73
4.00' LT

STA. 72+67.19
51.22' LT

STA. 72+17.27
4.00' LT

STA. 72+79.63
8.94' LT

STA. 73+13.76
9.06' LT

STA. 73+21.62
50.12' LT

STA. 73+21.62
4.00' LT

50' R

12'

17'

68 69 70+00 71 72 73 0+00

STA. 72+21.96
20.00' RT

STA. 72+82.62
50.40' RT

STA. 73+21.62
50.11' RT

STA. 73+21.62
20.00' RT

14' R

STA. 72+71.81
66.14' RT

STA. 73+21.62
67.21' RT

11'

0' 20' 40'
SCALE

FILE NAME = c:\pw_work\pwidot\aubreygs\d0346345\D468683-stagrng.dgn	USER NAME = aubreygs	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
Stage IB	PLOT DATE = 1/29/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

STAGE IB PLAN

SCALE: | SHEET OF SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
6584	105: (72-7HB)BY	PEORIA	487	150
		CONTRACT NO. 68683		
	ILLINOIS FED. AID PROJECT			