				CONSTRUCTION CODE												
			URBAN	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (STATE/CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)	
				ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT IL 6 RAMPS	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0003	0013	0040	0021	0021	0021	0028	0021	0021	0043	0043	0003	0042
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	57	38						19						
42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	15518	15518												
42000316	PORTLAND CEMENT CONCRETE PAVEMENT 8 3/4" (JOINTED)	SQ YD	18975	18975												
42001300	PROTECTIVE COAT	SQ YD	34582	34582												
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	88	88												
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	348	348												
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	2725								2725					
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	1819							1819						
42400800	DETECTABLE WARNINGS	SQ FT	148							148						
44000100	PAVEMENT REMOVAL	SQ YD	29347	29032						315						
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	924	924												
44000400	GUTTER REMOVAL	FOOT	853	853												
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2842	2842												