

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												
				URBAN	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (FED/STATE)	80/20 (STATE/CITY)	80/20 (FED/CITY)	100% (STATE)	100% (CITY OF PEORIA)	100% (STATE)
				ROADWAY	SN 072-0146	SN 072-7004	SIGNALS AT IL 6 RAMP	LIGHTING	SIGNING	MULTI-USE PATH	SIDEWALK	SIGNALS VAN WINKLE WAY	WATER MAIN	WATER MAIN	MOWING	TRAINEES
51200957	FURNISHING METAL SHELL PILES 12" X 0.250"	FOOT	969													
51200959	FURNISHING METAL SHELL PILES 14" X 0.312"	FOOT	441													
51202305	DRIVING PILES	FOOT	1410													
51203200	TEST PILE METAL SHELLS	EACH	2													
51500100	NAME PLATES	EACH	2													
52000110	PREFORMED JOINT STRIP SEAL	FOOT	174													
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24													
52100520	ANCHOR BOLTS, 1"	EACH	48													
52100530	ANCHOR BOLTS, 1 1/4"	EACH	6													
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2													
54003000	CONCRETE BOX CULVERTS	CU YD	400.3													
54010303	PRECAST CONCRETE BOX CULVERTS 3' X 3'	FOOT	7													
5421D012	PIPE CULVERTS, CLASS D, TYPE 112" (TEMPORARY)	FOOT	105													
5421D015	PIPE CULVERTS, CLASS D, TYPE 115" (TEMPORARY)	FOOT	156													

FILE NAME :	USER NAME : aubreyga	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ALLEN ROAD IMPROVEMENTS SUMMARY OF QUANTITIES				F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
e:\gen\draft\td\pln\squad\allen rd\final sheet revisions\0469083-shr-S00.dgn	DRAWN -	REVISED -	6584						105: (72-7HB)BY	PEORIA	487	15	
PLOT SCALE = 20:0000' / in.	CHECKED -	REVISED -	6585		CONTRACT NO. 68683								
PLT DATE = 11/31/2014 1:52:00 PM	DATE -	REVISED -	SCALE: SHEET OF SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT						