TABULATION OF RESURFACING QUANTITIES

LOCATION	TOTAL ROADWAY WIDTH (FOOT)	LENGTH (FOOT)	AREA (SQ YD)	HMA SURFACE REMOVAL BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	HMA SURFACE REMOVAL 3/4" (SQ YD)	HMA SURFACE REMOVAL VAR. DEPTH (SQ YD)	POLY. BIT MATERIALS PRIME COAT (TON)	POLY HMA SURFACE CSE MIX D N50 (TON)	INCIDENTAL HMA SURFACE (TON)	HMA SURFACE COURSE MIX C N50				AGGREGATE WEDGE SHOULDERS, TYPE B			
											LEFT AREA SQ YD	LEFT SIDE TON	RIGHT AREA SQ YD	RIGHT SIDE TON	LEFT AREA SQ YD	LEFT SIDE TON	RIGHT AREA SQ YD	RIGHT SIDE TON
MAIN LINE																		
STA. 427 + 58 TO 427 + 88	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
STA. 427 + 88 TO 433 + 05	24.00	517.00	1378.67			1378.67		0.55	155.48						172.33	19.63	172.33	19.63
STA. 433 + 05 TO 439 + 06	30.00	601.00	2003.33			2003.33		0.80	225.62						200.33	22.82	200.33	22.82
STA. 439 + 06 TO 476 + 75	36.00	3769.00	15076.00			15076.00		6.03	1696.33						1256.33	143.08	1256.33	143.08
STA. 476 + 75 TO 479 + 77	30.00	302.00	1006.67			1006.67		0.40	113.37						100.67	11.46	100.67	11.46
STA. 479 + 77 TO 504 + 90	24.00	2513.20	6701.87			6701.87		2.68	755.82						837.73	95.41	837.73	95.41
STA. 504 + 90 TO 507 + 32	33.50	242.32	901.97			901.97		0.36	101.52						80.77	9.20	80.77	9.20
STA. 507 + 32 TO 509 + 15	46.25	182.27	936.67			936.67		0.37	105.28						60.76	6.92	60.76	6.92
STA. 509 + 15 TO 516 + 38	38.00	723.49	3054.74			3054.74		1.22	343.63						241.16	27.47	241.16	27.47
STA. 516 + 38 TO 520 + 65	31.00	427.00	1470.78			1470.78		0.59	165.61						142.33	16.21	142.33	16.21
STA. 520 + 65 TO 533 + 47	24.00	1282.34	3419.57			3419.57		1.37	385.65						427.45	48.68	427.45	48.68
STA. 533 + 47 TO 533 + 77	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
STA. 533 + 77 TO 540 + 45	BRIDGE OMISSION																	
STA. 540 + 45 TO 540 + 75	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
STA. 540 + 75 TO 615 + 63	24.00	7487.53	19966.75			19966.75		7.99	2251.81						2495.84	284.25	2495.84	284.25
STA. 615 + 63 TO 615 + 93	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
STA. 615 + 93 TO 617 + 76	BRIDGE OMISSION																	
STA. 617 + 76 TO 618 + 06	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
STA. 618 + 06 TO 669 + 52	24.00	5145.97	13722.59			13722.59		5.49	1547.60						1715.32	195.36	1715.32	195.36
STA. 669 + 52 TO 669 + 82	24.00	30.00	80.00	80.00	13.33			0.03	9.02						10.00	1.14	10.00	1.14
HMA SHOULDERS																		
LT&RT STA. 427 + 58 TO 458 + 84	8.00	3126.00				2778.67		1.11			1389.33	158.85	1389.33	158.85				
LT STA. 458 + 84 TO 461 + 85	4.00	300.66				133.63		0.05			133.63	15.28						
RT STA. 458 + 84 TO 473 + 48	8.00	1463.09					1300.52	0.52					1300.52	147.18				
LT STA. 461 + 85 TO 479 + 28	4.00	1742.78					774.57	0.31			774.57	88.56						
RT STA. 473 + 48 TO 476 + 85	8.00	337.57				300.06		0.12					300.06	33.96				
RT STA. 476 + 85 TO 479 + 77	8.00	291.99					259.55	0.10					259.55	29.37				
LT STA. 479 + 28 TO 479 + 77	4.00	49.21				21.87		0.01			21.87	2.50						
LT&RT STA. 479 + 77 TO 481 + 12	12.00	134.52				59.79	119.57	0.07			59.79	6.84	119.57	13.53				
LT&RT STA. 481 + 12 TO 483 + 58	12.00	246.06				328.08		0.13			109.36	12.50	218.72	24.75				
LT&RT STA. 483 + 58 TO 485 + 60	12.00	202.43				89.97	179.94	0.11			89.97	10.29	179.94	20.36				
LT STA. 485 + 60 TO 490 + 93	8.00	532.48				473.32		0.19			473.32	53.56						
RT STA. 485 + 60 TO 487 + 96	8.00	235.73					209.54	0.08					209.54	23.71				
RT STA. 487 + 96 TO 490 + 93	8.00	296.75				263.78		0.11					263.78	29.85				
LT&RT STA. 490 + 93 TO 496 + 90	12.00	597.11				796.15		0.32			530.76	60.06	265.38	30.34				
LT&RT STA. 496 + 90 TO 507 + 86	8.00	1096.33				974.52		0.39			487.26	55.71	487.26	55.71				
LT&RT STA. 507 + 86 TO 511 + 85	12.00	399.10				177.38	354.76	0.21			354.76	40.15	177.38	20.28				
LT&RT STA. 511 + 85 TO 531 + 74	8.00	1988.83				1767.85		0.71			883.92	101.06	883.92	101.06				
LT&RT STA. 531 + 74 TO 532 + 07	16.00	32.80				58.31		0.02			29.16	3.30	29.16	3.30				
LT&RT STA. 532 + 07 TO 533 + 77	16.00	170.34					302.83	0.12			151.41	17.13	151.41	17.13				
STA. 533 + 77 TO 540 + 45	BRIDGE OMISSION																	
LT&RT STA. 540 + 45 TO 541 + 98	16.00	153.19					272.34	0.11			136.17	15.41	136.17	15.41				
LT&RT STA. 541 + 98 TO 542 + 35	16.00	37.10				65.96		0.03			32.98	3.73	32.98	3.73				
LT&RT STA. 542 + 35 TO 613 + 94	8.00	7159.23				6363.76		2.55			3181.88	363.79	3181.88	363.79				
RT STA. 613 + 94 TO 614 + 37	8.00	42.65				37.91		0.02					37.91	4.29				
LT STA. 613 + 94 TO 615 + 19	4.00	124.35				55.27		0.02			55.27	6.32						
RT STA. 614 + 37 TO 615 + 93	8.00	155.65					138.36	0.06					138.36	15.66				
LT STA. 615 + 19 TO 615 + 61	8.00	42.65				37.91		0.02			37.91	4.29						
LT STA. 615 + 61 TO 615 + 93	8.00	31.30					27.82	0.01			27.82	3.15						
STA. 615 + 93 TO 617 + 76	BRIDGE OMISSION																	
RT STA. 617 + 76 TO 618 + 07	8.00	30.65					27.24	0.01					27.24	3.08				
LT STA. 617 + 76 TO 619 + 32	8.00	155.64					138.35	0.06			138.35	15.66						
RT STA. 618 + 07 TO 619 + 21	8.00	114.03				101.36		0.04					101.36	11.47				
SUB-TOTAL				**480**	**80**	**84,525**	**4,105**	**35.6**	**7,902**		**9,099**	**1,038**	**9,891**	**1,127**	**7,791**	**887**	**7,791**	**887**
												SUB-TOTAL	**18,991**	**2,165**		**SUB-TOTAL**	**15,582**	**1,775**

FILE NAME =	USER NAME = mendezpj	DESIGNED -	REVISED -
S:\GEN\DRAFT\STD&PLNS\SQUAD11\68980\D468980 Plans.dgn		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 2/3/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULE

SCALE: | SHEET 1 OF 2 SHEETS | STA. TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	(104,105)RS-4	MERCER	32	15

CONTRACT NO. 68980

ILLINOIS FED. AID PROJECT