

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80% FED 20% STATE	CONSTRUCTION CODE
				0005	
28100809	STONE DUMPED RIPRAP, CLASS A5	TON	280	280	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	39.23	39.23	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	766	766	
40600990	TEMPORARY RAMP	SO YD	209	209	
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2889	2889	
40603535	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	8038	8038	
40800050	INCIDENTAL HOT - MIX ASPHALT SURFACING	TON	282	282	
44000152	HOT - MIX ASPHALT SURFACE REMOVAL, 3/4"	SO YD	90274	90274	
44201815	CLASS D PATCHES, TYPE II, 14 INCH	SO YD	104	104	
44201821	CLASS D PATCHES, TYPE IV, 14 INCH	SO YD	40	40	
48102100	AGGREGATE WEDGE SHOULDERS, TYPE B	TON	1775	1775	
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	6	6	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	

FILE NAME *	USER NAME * mendej	DESIGNED -	REVISED -
S:\GEN\DRIFT\STO&PLNS\EGUAD\1\68980\04	8980 Plans\jdn	DRAWN -	REVISED -
	PLOT SCALE = 40,0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 1/30/2014	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	1104,105,RS-4	MERCER	32	4
			CONTRACT NO. 68980	
ILLINOIS FED. AID PROJECT				