

EROSION AND SEDIMENT CONTROL SCHEDULE		
LOCATION	INLET AND PIPE PROTECTION (EACH)	EROSION CONTROL BLANKET (SQ. YD.)
STA. 21+00 TO STA. 21+40	2	296
TOTAL	2	296

MANHOLES, TYPE A, 7'-DIAMETER, WITH SPECIAL FRAME AND GRATE	
LOCATION	EACH
STA. 21+23.5, 51.00' LT	1
TOTAL	1

AGGREGATE SURFACE COURSE, TYPE B	
LOCATION	TON
STA. 23+36 RT	9
TOTAL	9

TOPSOIL FURNISH & PLACE, 4"	
LOCATION	SQ. YD.
STA. 21+00 TO 21+40 LT & RT	296
TOTAL	296

PRECAST REINF. CONC. FLARED END SECTIONS 42"	
LOCATION	EACH
STA. 21+23.5, 53.64' RT	1
TOTAL	1

INSERTION CULVERT LINER 42"	
LOCATION	FOOT
STA. 21+34, LT	8
TOTAL	8

FILLING EXISTING CULVERTS		
LOCATION	OFFSET	CU. YD.
STA. 21+05	25.58' RT TO 48.98' RT	2.7
STA. 21+05	24.42' LT TO 25.58' RT	7.4
STA. 21+05 TO STA. 21+18	45.85' LT TO 24.42' LT	5.0
TOTAL		15

PIPE CULVERTS, CLASS A, TYPE 2 42"	
LOCATION	FOOT
STA. 21+23.5, RT	14
TOTAL	14

PIPE CULVERTS, CLASS A, 42" (JACKED)	
LOCATION	FOOT
STA. 21+23.5, 48.47' LT TO 31.47' RT	80.0
TOTAL	80

REMOVAL OF EXISTING STRUCTURES NO. 1	
LOCATION	EACH
STA. 21+21.5, 48.0' LT	1
TOTAL	1

PIPE CULVERT REMOVAL	
LOCATION	FOOT
STA. 23+36 RT	56
TOTAL	56

CONCRETE COLLAR SCHEDULE		
LOCATION	CONCRETE COLLAR (CU. YD.)	REINFORCEMENT BARS (POUND)
STA. 21+23.5, 31.47' RT	1.1	50
TOTAL	1.1	50

REMOVE EXISTING FLARED END SECTION	
LOCATION	EACH
STA. 21+05 RT	1
TOTAL	1

TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

GRADING AND SHAPING DITCHES	
LOCATION	FOOT
STA. 21+00 TO 21+40 RT	40
TOTAL	40

MOBILIZATION	
LOCATION	L SUM
JOBSITE	1
TOTAL	1

RIPRAP SCHEDULE			
LOCATION	DIMENSIONS	STONE RIPRAP, CLASS A4 (SQ. YD.)	FILTER FABRIC (SQ. YD.)
STA. 21+23.5 RT	13'x13'	19	19
TOTAL		19	19

FILE NAME = Farmington Culvert Repair Plan - Revisions due to Cattle Farmer Stubborness April 2014
 USER NAME = aubreys
 DESIGNED - KJH
 DRAWN - JGJ
 CHECKED - KJH
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	17CR	PEORIA	20	8
CONTRACT NO. 68B27				
ILLINOIS FED. AID PROJECT				