

## SCHEDULE OF QUANTITIES

### MCDONOUGH COUNTY

| ITEM DESCRIPTION  | UNIT  | TOTAL QTY. | MCDONOUGH COUNTY  |   |  |  |   |  |   |  |  |  |  |      |
|---|-------|------------|---|---|--|--|---|--|---|--|--|--|--|------|
|   |       |            | US 67/US 136<br>(E. JACKSON)<br>& WHEELER<br>0% IDOT<br>100% CITY | US 67/US 136<br>(E. JACKSON)<br>& PRAIRIE<br>50% IDOT<br>50% CITY | US 67/US 136<br>(E. JACKSON)<br>& DUDLEY<br>50% IDOT<br>50% CITY | US 67/US 136<br>(E. JACKSON)<br>& CAMPBELL<br>50% IDOT<br>50% CITY | US 67/US 136<br>(CALHOUN) &<br>CAMPBELL<br>50% IDOT<br>50% CITY | US 67<br>(LAFAYETTE)<br>& US 67<br>(CALHOUN)<br>100% IDOT<br>0% CITY | US 136<br>(W. JACKSON)<br>& JOHNSON<br>50% IDOT<br>50% CITY | US 136<br>(W. JACKSON)<br>& WARD<br>50% IDOT<br>50% CITY | US 136<br>(W. JACKSON)<br>& WIGWAM<br>HOLLOW<br>50% IDOT<br>50% CITY | US 67<br>(LAFAYETTE)<br>& PIERCE<br>50% IDOT<br>50% CITY | US 67<br>(LAFAYETTE)<br>& UNIVERSITY<br>50% IDOT<br>50% CITY |      |
| MOBILIZATION  | L SUM | 1.0        | 0.08  | 0.08  | 0.08   | 0.08   | 0.08  | 0.20   | 0.08  | 0.08   | 0.08   | 0.08   | 0.08   | 0.08 |
| TRAFFIC CONTROL AND PROTECTION, STANDARD 701602                           | L SUM | 1.0        | 0.08  | 0.08  | 0.08   | 0.08   | 0.08  | 0.20   | 0.08  | 0.08   | 0.08   | 0.08   | 0.08   | 0.08 |
| TRAFFIC CONTROL AND PROTECTION, STANDARD 701701                           | L SUM | 1.0        | 0.08  | 0.08  | 0.08   | 0.08   | 0.08  | 0.20   | 0.08  | 0.08   | 0.08   | 0.08   | 0.08   | 0.08 |
| SIGN PANEL - TYPE 1   | SQ FT | 105.0      | 20.0  | 10.0  | 5.0  |  |   | 10.0   |   | 10.0   | 10.0   | 20.0   | 20.0   |      |
| RAILROAD, FULL-ACTUATED CONTROLLER AND TYPE V CABINET                     | EACH  | 1.0        |   |   |  |  |   | 1.0  |   |  |  |  |  |      |
| FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM12F                   | FOOT  | 3994.0     |   |   |  |  |   | 3994.0   |   |  |  |  |  |      |
| ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C                               | FOOT  | 213.0      |   |   |  |  |   |  |   | 213.0  |  |  |  |      |
| ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C                               | FOOT  | 4032.0     | 1157.0  | 289.0   |  |  |   |  |   | 500.0  | 405.0  | 857.0  | 824.0  |      |
| ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C                               | FOOT  | 544.0      |   |   |  |  |   |  |   | 544.0  |  |  |  |      |
| SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED                     | EACH  | 51.0       |   | 6.0   | 8.0  | 4.0  | 5.0   | 4.0  | 8.0   | 4.0  |  | 6.0  | 6.0  |      |
| SIGNAL HEAD, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED                      | EACH  | 26.0       | 2.0   | 2.0   |  | 4.0  | 5.0   | 3.0  | 4.0   | 2.0  |  | 2.0  | 2.0  |      |
| SIGNAL HEAD, LED, 1-FACE, 4-SECTION, BRACKET MOUNTED                      | EACH  | 17.0       |   | 2.0   | 1.0  |  |   | 2.0  |   | 4.0  |  | 4.0  | 4.0  |      |
| SIGNAL HEAD, LED, 1-FACE, 4-SECTION, MAST ARM MOUNTED                     | EACH  | 24.0       |   | 2.0   | 1.0  | 3.0  | 3.0   | 2.0  | 3.0   | 2.0  |  | 4.0  | 4.0  |      |
| SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED                      | EACH  | 5.0        |   |   |  | 1.0  |   | 1.0  | 3.0   |  |  |  |  |      |
| PEDESTRIAN SIGNAL HEAD, LED, 1-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER | EACH  | 13.0       |   |   |  | 2.0  | 2.0   | 5.0  | 2.0   |  | 2.0  |  |  |      |

|  |  |                  |                 |
|--|--|------------------|-----------------|
| FILE NAME =                            | USER NAME = aubreys                    | DESIGNED - _____ | REVISED - _____ |
| C:\Users\aubreys\Desktop\68B61\68B61 - | Macomb FYA Project (Final 1-31-14).dgn | DRAWN - _____    | REVISED - _____ |
|  | PLOT SCALE = 38.0588' / in.            | CHECKED - _____  | REVISED - _____ |
|  | PLOT DATE = 1/31/2014                  | DATE - _____     | REVISED - _____ |

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: \_\_\_\_\_ STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

| F.A.P. RTE.               | SECTION                              | COUNTY    | TOTAL SHEETS | SHEET NO. |
|---------------------------|--------------------------------------|-----------|--------------|-----------|
| 310<br>315                | D4 FLASHING<br>YELLOW ARROWS<br>2013 | MCDONOUGH | 24           | 5         |
| CONTRACT NO. 68B61        |                                      |           |              |           |
| ILLINOIS FED. AID PROJECT |                                      |           |              |           |