

SCHEDULE OF QUANTITIES (CONTINUED)

MCDONOUGH COUNTY

ITEM DESCRIPTION	UNIT	TOTAL QTY.	US 67/US 136 (E. JACKSON) & WHEELER 0% IDOT 100% CITY	US 67/US 136 (E. JACKSON) & PRAIRIE 50% IDOT 50% CITY	US 67/US 136 (E. JACKSON) & DUDLEY 50% IDOT 50% CITY	US 67/US 136 (E. JACKSON) & CAMPBELL 50% IDOT 50% CITY	US 67/US 136 (CALHOUN) & CAMPBELL 50% IDOT 50% CITY	US 67 (LAFAYETTE) & US 67 (CALHOUN) 100% IDOT 0% CITY	US 136 (W. JACKSON) & JOHNSON 50% IDOT 50% CITY	US 136 (W. JACKSON) & WARD 50% IDOT 50% CITY	US 136 (W. JACKSON) & WIGWAM HOLLOW 50% IDOT 50% CITY	US 67 (LAFAYETTE) & PIERCE 50% IDOT 50% CITY	US 67 (LAFAYETTE) & UNIVERSITY 50% IDOT 50% CITY
			PEDESTRIAN SIGNAL HEAD, LED, 2-FACE, BRACKET MOUNTED WITH COUNTDOWN TIMER	EACH	39.0	4.0	4.0	4.0	4.0	4.0	2.0	4.0	4.0
TRAFFIC SIGNAL BACKPLATE, RETROREFLECTIVE	EACH	79.0		8.0	9.0	7.0	8.0	6.0	11.0	10.0		10.0	10.0
INDUCTIVE LOOP DETECTOR	EACH	62.0			12.0			20.0		10.0		10.0	10.0
REBUILD EXISTING SIGNAL HEAD, LED	EACH	12.0	8.0								4.0		
MODIFY EXISTING CONTROLLER CABINET	EACH	3.0	1.0	1.0							1.0		
MODIFY EXISTING TRAFFIC SIGNAL BACKPLATE	EACH	25.0	10.0			2.0		4.0			9.0		
CAT 5 ETHERNET CABLE	FOOT	318.0				231.0			87.0				
CLOSED CIRCUIT TELEVISION DOME CAMERA, IP BASED (INSTALL ONLY)	EACH	2.0				1.0			1.0				
FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	4.0			1.0					1.0		1.0	1.0
CONTROLLER CABINET TYPE IV, SPECIAL	EACH	3.0				1.0	1.0		1.0				
STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT. (SPECIAL)	EACH	1.0								1.0			
STEEL MAST ARM ASSEMBLY AND POLE, 38 FT. (SPECIAL)	EACH	1.0								1.0			
SIGNAL HEAD, LED, RETROFIT	EACH	22.0	7.0			2.0		5.0			8.0		
TRAFFIC SIGNAL BATTERY BACKUP SYSTEM	EACH	1.0						1.0					
RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1.0						1.0					

FILE NAME =	USER NAME = aubreys	DESIGNED - _____	REVISED - _____
C:\Users\aubreys\Desktop\68B61\68B61 -	Macomb FYA Project (Final 1-31-14).dgn	DRAWN - _____	REVISED - _____
	PLOT SCALE = 38.0588' / in.	CHECKED - _____	REVISED - _____
	PLOT DATE = 1/31/2014	DATE - _____	REVISED - _____

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES (CONTINUED)

SCALE: _____ STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310 315	D4 FLASHING YELLOW ARROWS 2013	MCDONOUGH	24	6
CONTRACT NO. 68B61				
ILLINOIS FED. AID PROJECT				