

GENERAL NOTES

SIGN LOCATIONS MAY VARY FROM THE STATIONS SHOWN ON THE PLANS IN ACCORDANCE WITH DIRECTIONS FROM THE ENGINEER AT THE TIME OF CONSTRUCTION. SIGN LOCATIONS MAY BE ADJUSTED IN THE FIELD TO AVOID ANY FOUND UTILITIES.

ALL WOOD POST LOCATIONS SHALL BE VERIFIED WITH THE BUREAU OF OPERATIONS, TRAFFIC SECTION, BEFORE INSTALLATION.

JOB SPECIFIC NOTES

CHEVRONS SHALL BE PLACED OUTSIDE OF EXISTING SHOULDERS WIDTHS AS GIVEN IN THE SCHEDULE OF QUANTITIES.

ALL SIGN PANELS SHALL BE BOLTED TO METAL POSTS WITH STAINLESS STEEL FASTENERS.

CONTACT TRAFFIC OPERATIONS AREA TECHNICIANS BEFORE ANY METAL POSTS ARE PLACE TO VERIFY LOCATIONS:

TRAFFIC OPERATIONS EAST AREA TECHNICIAN:

BILL HARRMANN (309) 370-7513

COMMITMENTS

THERE ARE NO COMMITMENTS FOR THIS PROJECT.

FILE NAME =	USER NAME = jonesros	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS GENERAL NOTES	F.A.I.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
S:\GEN\DRAW\STD&PLNS\SQUAD13\Leo Projects\I-39 & US 24 Kingston Mine\Plansheets.dwg	PLotted	DRAWN -	REVISED -			39,317	•	VARIOUS	15	2	
Default	PLOT SCALE = 80.0000' / in.	CHECKED -	REVISED -			CONTRACT NO. 68B68					
	PLOT DATE = 2/6/2014	DATE -	REVISED -			SCALE:	SHEET	OF	SHEETS	STA.	TO