

LOCATION	PAVEMENT REMOVAL (SQ. YD.)	HMA BINDER COURSE, IL-12.5, N50 (TON)	HMA SURFACE COURSE, MIX "D", N50 (TON)	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"		SHORT TERM PAVEMENT MARKING (FT.)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ. FT.)	INLET FILTERS (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)
				WHITE (FT.)	YELLOW (FT.)				
IL ROUTE 29 STA. 1552+81 TO STA. 1558+51	1400	588	157	1140	1140	60	20	6	8
TOTAL	1400	588	157	2280		60	20	6	8

LOCATION	MOBILIZATION (L. SUM)	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21 (L. SUM)	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201 (L. SUM)	RAILROAD PROTECTIVE LIABILITY INSURANCE (L. SUM)	CHANGEABLE MESSAGE SIGN (CAL. MO.)
IL ROUTE 29 ENTIRE JOBSITE	1	1	1	1	1
TOTAL	1	1	1	1	1

LOCATION	EARTH EXCAVATION (CU. YD.)
IL ROUTE 29 STA. 1557+20 TO STA. 1558+51	55
TOTAL	55

NOTE: ALL THE EARTH EXCAVATION WILL BE WASTE.

FILE NAME = mikejvioduct.dgn	USER NAME = keathbr	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
318	6-1	PEORIA	6	5
CONTRACT NO. 68B72				
ILLINOIS FED. AID PROJECT				