



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

04/15/2014

SUBJECT: FAB Route 322 (US 51)
Project ACNHPP-0322 (100)
Section 54 B-3, 54B-2
Dewitt County
Contract No. 70606
Item No. 047, April 25th, 2014 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices
2. Revised Plans Sheet No. 6
3. Revised Table of Contents of Special Provisions Pages i,ii
4. Revised Page (20) of the Special Provisions
5. Added Page (129) to the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E." with a small "P.E." to the right.

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 5; Tim Kell; D. Carl Puzey; Estimates

HM/kp

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 70606

State Job # - C-95-120-06

County Name - DEWITT -
 Code - 39 - -
 District - 5 - -
 Section Number - 54B-3, 54B-2

Project Number
 ACNHPP-0322/100/
 *REVISED: APRIL 9, 2014

Route
 FAP 322

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
*ADD X7010410	SPEED DISPLAY TRAILER	CAL MO	5.000				
X7015005	CHANGEABLE MESSAGE SN	CAL DA	14.000				
X7200201	WIDTH RESTRICT SIGN	L SUM	1.000				
Z0001495	BR APPROACH SHLD REM	SQ YD	29.000				
Z0001800	APPROACH SL REP (PD)	SQ YD	11.000				
Z0012754	STR REP CON DP = < 5	SQ FT	72.000				
Z0073700	TEMP WALL BRACING SYS	L SUM	1.000				
20400800	FURNISHED EXCAVATION	CU YD	40.000				
25000210	SEEDING CL 2A	ACRE	0.250				
25000400	NITROGEN FERT NUTR	POUND	22.500				
25000500	PHOSPHORUS FERT NUTR	POUND	22.500				
25000600	POTASSIUM FERT NUTR	POUND	22.500				
25100115	MULCH METHOD 2	ACRE	0.250				
28000250	TEMP EROS CONTR SEED	POUND	25.000				
28000305	TEMP DITCH CHECKS	FOOT	130.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 70606

State Job # - C-95-120-06

County Name - DEWITT -

Code - 39 - -

District - 5 - -

Section Number - 54B-3, 54B-2

Project Number
 ACNHPP-0322/100/
 *REVISED: APRIL 9, 2014

Route
 FAP 322

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
28000400	PERIMETER EROS BAR	FOOT	633.000				
28000500	INLET & PIPE PROTECT	EACH	2.000				
28100105	STONE RIPRAP CL A3	SQ YD	32.000				
40603345	HMA SC "D" N90	TON	75.000				
42001500	PCC BR APPR SHLD PAVT	SQ YD	29.000				
44000300	CURB REM	FOOT	187.000				
48101200	AGGREGATE SHLDS B	TON	43.000				
50101500	REM EXIST SUP-STR	EACH	2.000				
50102400	CONC REM	CU YD	1.100				
50105220	PIPE CULVERT REMOV	FOOT	36.000				
50300225	CONC STRUCT	CU YD	1.200				
50400505	P P CONC DK BM 27 DP	SQ FT	5,282.000				
50800205	REINF BARS, EPOXY CTD	POUND	80.000				
50901050	STEEL RAILING TY SM	FOOT	252.000				
51500100	NAME PLATES	EACH	2.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER -

70606

State Job # - C-95-120-06

County Name - DEWITT -

Code - 39 - -

District - 5 - -

Section Number - 54B-3, 54B-2

Project Number
 ACNHPP-0322/100/
 *REVISED: APRIL 9, 2014

Route
 FAP 322

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
542A1057	P CUL CL A 2 12	FOOT	30.000				
54213657	PRC FLAR END SEC 12	EACH	1.000				
58100200	WATERPRF MEMBRANE SYS	SQ YD	594.000				
58300100	PC MORTAR FAIRING CSE	FOOT	1,446.000				
60262700	INLETS RECONST	EACH	1.000				
63000001	SPBGR TY A 6FT POSTS	FOOT	750.000				
63100045	TRAF BAR TERM T2	EACH	4.000				
63100087	TRAF BAR TERM T6A	EACH	8.000				
63100169	TR BAR TRM T1 SPL FLR	EACH	4.000				
63200310	GUARDRAIL REMOV	FOOT	1,328.000				
67000500	ENGR FIELD OFFICE B	CAL MO	7.000				
67100100	MOBILIZATION	L SUM	1.000				
70100207	TRAF CONT-PROT 701402	EACH	2.000				
70100420	TRAF CONT-PROT 701411	EACH	2.000				
70100700	TRAF CONT-PROT 701406	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 70606

State Job # - C-95-120-06

County Name - DEWITT - -

Code - 39 - -

District - 5 - -

Section Number - 54B-3, 54B-2

Project Number

ACNHPP-0322/100/

*REVISED: APRIL 9, 2014

Route

FAP 322

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70300220	TEMP PVT MK LINE 4	FOOT	3,035.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	4,423.000				
70400100	TEMP CONC BARRIER	FOOT	575.000				
70400200	REL TEMP CONC BARRIER	FOOT	575.000				
70600250	IMP ATTN TEMP NRD TL3	EACH	2.000				
70600350	IMP ATTN REL NRD TL3	EACH	2.000				
78001110	PAINT PVT MK LINE 4	FOOT	3,035.000				
78200410	GUARDRAIL MKR TYPE A	EACH	22.000				
78201000	TERMINAL MARKER - DA	EACH	4.000				
78300100	PAVT MARKING REMOVAL	SQ FT	969.000				

INTENT OF PROJECT 1
DESCRIPTION OF PROJECT..... 1
TRAFFIC CONTROL PLAN..... 1
INITIAL INSTALLATION OF CONCRETE BARRIER: 4
RELOCATION OF CONCRETE BARRIER: 4
REMOVAL OF CONCRETE BARRIER: 4
PUBLIC NOTIFICATION..... 5
CHANGEABLE MESSAGE SIGN..... 5
TEMPORARY TRAFFIC CONTROL DEVICE DEPLOYMENT AND REMOVAL 6
WIDTH RESTRICTION AND MAXIMUM WIDTH SIGNING 6
AGGREGATE SHOULDERS, TYPE B..... 7
APPROACH SLAB REPAIR..... 7
BRIDGE APPROACH SHOULDER REMOVAL 12
FRICTION AGGREGATE 12
GUARDRAIL INSTALLATION TIME..... 15
GUARDRAIL REMOVAL AND INSTALLATION 15
HOT-MIX ASPHALT – REQUIRED FIELD TESTS..... 16
NON-VERTICAL IMPACT ROLLER FOR HOT-MIX ASPHALT 16
PNEUMATIC-TIRED ROLLER FOR HOT-MIX ASPHALT 16
SHEAR KEYS FOR PRECAST, PRESTRESSED CONCRETE DECK BEAMS..... 17
REPLACE 1006.06(A) AND (B) WITH THE FOLLOWING 19
STATUS OF UTILITIES..... 19
TEMPORARY WALL BRACING SYSTEM 21
PRECAST, PRESTRESSED CONCRETE DECK BEAMS 21
CONCRETE DECK BEAMS 24
COARSE AGGREGATE IN BRIDGE APPROACH SLABS/FOOTINGS (BDE) 26
CONCRETE END SECTIONS FOR PIPE CULVERTS (BDE) 26
CONCRETE MIX DESIGN – DEPARTMENT PROVIDED (BDE) 28
CONTRACT CLAIMS (BDE)..... 28
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 29
HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)..... 38

HOT-MIX ASPHALT – MIXTURE DESIGN COMPOSITION AND VOLUMETRIC REQUIREMENTS (BDE) 39
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (BDE)..... 41
LRFD PIPE CULVERT BURIAL TABLES (BDE) 44
PAVEMENT MARKING FOR BIKE SYMBOL (BDE)..... 63
PAYROLLS AND PAYROLL RECORDS (BDE) 63
PORTLAND CEMENT CONCRETE EQUIPMENT (BDE)..... 65
PROGRESS PAYMENTS (BDE) 65
RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE)..... 66
REINFORCEMENT BARS (BDE) 75
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (BDE)..... 77
REMOVAL AND DISPOSAL OF SURPLUS MATERIALS (BDE)..... 80
TRACKING THE USE OF PESTICIDES (BDE)..... 81
WARM MIX ASPHALT (BDE) 81
WEEKLY DBE TRUCKING REPORTS (BDE)..... 85
WORKING DAYS (BDE)..... 85
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID)..... 85
404 PERMIT 89
SPEED DISPLAY TRAILER (BDE)..... 129

Revised 04/15/2014

FAP Route 322 (US 51)
Project ACNHPP-0322 (100)
Section 54B-3, 54B-2
DEWITT County
Contract No 70606
Not required

Mr. Robert Zuege Along east ROW
* Ameren Illinois
Mail Code K-30
2460 North Jasper Street
Decatur, IL 62521
(217) 424-7075

NOTE: No utility coordination has been done on this project.

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Sections 102, 103, and Articles 105.07, 107.20, 107.31, and 108.02 of the Standard Specifications for Road and Bridge Construction shall apply.

The estimated utility relocation dates should be part of the progress schedule submitted by the contractor. If any utility adjustments or relocations have not been completed by the above dates specified and when required by the contractor's operations after these dates, the contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's critical path schedule is affected.

Toll Free J.U.L.I.E. Telephone Number (800) 892-0123 or 811
* = J.U.L.I.E. Member

Revised 04/15/2014

SPEED DISPLAY TRAILER (BDE)

Effective: April 2, 2014

Add the following to Article 701.15(l) of the Standard Specifications:

- “ (l) Speed Display Trailer. A speed display trailer shall be utilized on freeways and expressways as part of Highway Standard 701400. The trailer shall be placed on the right hand side of the roadway adjacent to, or within 100 ft (30 m) beyond, the first work zone speed limit sign.

Whenever the speed display trailer is not in use, it shall be considered non-operating equipment and shall be stored according to Article 701.11.”

Add the following to Article 701.20 of the Standard Specifications:

- “ (k) Speed Display Trailer will be paid for at the contract unit price per calendar month or fraction thereof for each trailer as SPEED DISPLAY TRAILER.”

Add the following to Article 1106.02 of the Standard Specifications:

- “ (o) Speed Display Trailer. The speed display trailer shall consist of a LED speed indicator display with self-contained, one-direction radar mounted on an orange see-through trailer. The height of the display and radar shall be such that it will function and be visible when located behind concrete barrier.

The speed measurement shall be by radar and provide a minimum detection distance of 1000 ft (300 m). The radar shall have an accuracy of ± 1 mile per hour.

The speed indicator display shall face approaching traffic and shall have a sign legend of “YOUR SPEED” immediately above or below the speed display. The digital speed display shall show two digits (00 to 99) in mph. The color of the changeable message legend shall be a yellow legend on a black background. The minimum height of the numerals shall be 18 in. (450 mm), and the nominal legibility distance shall be at least 750 ft (250 m).

The speed indicator display shall be equipped with a violation alert that flashes the displayed detected speed when the posted limit is exceeded. The speed indicator shall have a maximum speed cutoff. The display shall include automatic dimming for nighttime operation.

The speed indicator measurement and display functions shall be equipped with the power supply capable of providing 24 hours of uninterrupted service.”

Added 04/15/2014