

SCHEDULE OF QUANTITIES

WORK ZONE PAVEMENT MARKING REMOVAL						
					70301000	
PROFILE	OFFSET	STATION	TO	STATION	DESCRIPTION	SQ FT
NORTHBOUND	RT	1434+53.14		1440+12.75	TPM-4"	187
NORTHBOUND	RT	1434+39.32		1440+57.58	TPM-4"	207
NORTHBOUND	RT	1437+14.89		1437+82.02	TPM-4"	23
NORTHBOUND	RT	1422+79.93		1435+79.93	PRE-STAGE	434
NORTHBOUND	LT	1419+36.97		1438+39.19	TC&P (STAGE I)	635
NORTHBOUND	LT	1434+53.14		1440+12.75	TC&P (STAGE I)	187
NORTHBOUND	RT	1420+57.91		1438+39.33	TC&P (STAGE II)	594
NORTHBOUND	RT	1434+39.32		1440+57.58	TC&P (STAGE II)	207
SOUTHBOUND	LT	1433+73.20		1443+63.09	TPM-4"	330
SOUTHBOUND	LT	1435+52.63		1441+23.42	TPM-4"	191
SOUTHBOUND	LT	1437+22.29		1437+86.39	TPM-4"	22
SOUTHBOUND	LT	1447+81.47		1449+43.26	TPM-4"	54
SOUTHBOUND	LT	1447+59.00		1447+72.46	TC&P (STAGE I)	26
SOUTHBOUND	LT	1449+17.46		1449+43.26	TC&P (STAGE I)	30
SOUTHBOUND	LT	1449+43.26		1451+83.99	TC&P (STAGE I)	83
SOUTHBOUND	LT	1452+64.75		1459+43.06	TC&P (STAGE I)	228
SOUTHBOUND	LT	1433+73.20		1443+63.09	TC&P (STAGE II)	330
SOUTHBOUND	LT	1436+63.01		1444+40.67	TC&P (STAGE II)	265
SOUTHBOUND	LT	1447+59.42		1447+81.47	TC&P (STAGE II)	26
SOUTHBOUND	LT	1449+17.40		1449+43.26	TC&P (STAGE II)	30
SOUTHBOUND	LT	1449+43.26		1459+43.21	TC&P (STAGE II)	334
TOTAL						4423

TEMPORARY CONCRETE BARRIERS						
				70400100	70400200	
PROFILE	OFFSET	STATION	TO	STATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER
				FOOT	FOOT	
NORTHBOUND	RT	1435+22.37		1437+81.74	262.5	262.5
SOUTHBOUND	LT	1437+10.87		1440+29.64	312.5	312.5
TOTAL					575	575

IMPACT ATTENUATORS						
			70600250	70600350		
PROFILE	OFFSET	STATION	TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3		
			EACH	EACH		
NORTHBOUND	LT	1435+22.37	1			
SOUTHBOUND	LT	1440+29.64		1		
NORTHBOUND	RT	1435+22.41	1			
SOUTHBOUND	LT	1440+32.93		1		
TOTAL			2	2		

NOTE: OFFSET is based on looking upstation per the given profile.