

PAVEMENT MARKERS		
LOCATION	RAISED PAVEMENT MARKER REFLECTOR REPLACEMENT Z0049100 (EACH)	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) 78100105 (EACH)
CL 721+50.00 TO 729+08.75	10.0	
CL 729+08.75 TO 732+61.25		5.0
CL 732+61.25 TO 744+00.00	15.0	

PAVEMENT MARKING SCHEDULE			TEMPORARY PAVEMENT MARKING LINE 4" 70300220 (FOOT)	PAINT PAVEMENT MARKING LINE 4" 78001110 (FOOT)	SHORT-TERM PAVEMENT MARKING (FOOT)	PAVEMENT MARKING REMOVAL (SQ FT)	MODIFIED URETHANE PAVEMENT MARKING LINE 4" 78009004 (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	GROOVING FOR RECESSED PAVEMENT MARKING, 5" X7830070 (FOOT)
LOCATION									
RT	728+40	733+30	490.0			163.3		163.3	
LT	728+44	733+52	508.0			47.9		169.3	
⊕	726+70	735+23	213.2		85.3	27.7		99.5	
⊕	721+50	729+08.75			189.7				
LT/RT	721+50	729+08.75			1,517.5				
⊕	729+08.75	732+61.25					88.1		88.1
LT/RT	729+08.75	732+61.25					705.0		705.0
LT/RT	732+61.25	744+00			2,277.5				
⊕	732+61.25	742+70			252.2				
⊕	742+70	744+00			162.5				
TOTAL			1,211.2	4,399.4	85.3	238.9	793.1	432.1	793.1
ROUND TO:			1,215.0	4,400.0	100.0	240.0	795	435.0	795.0

PAVEMENT						
LOCATION	LENGTH (FOOT)	WIDTH* (FOOT)	PAVED SHOULDER REMOVAL 44004250 (SQ YD)	PAVEMENT REMOVAL 44000100 (SQ YD)	AGGREGATE SHOULDERS TYPE B 6" 48101500 (SQ YD)	BASE COURSE OPTION Z0002900 (SQ YD)
LT	721+50.00	723+39.93	189.93	VARIABLE	95.0	
LT	740+36.48	744+00.00	363.52	VARIABLE	196.0	
RT	729+02.75	729+88.80	86.05	VARIABLE	29.0	
RT	732+03.05	732+67.25	64.20	3.0	22.0	
RT	740+75.76	744+00.00	324.24	VARIABLE	166.0	
LT/RT	729+02.75	729+88.80	86.05	26		249.0
LT/RT	732+03.05	732+67.25	64.20	26		186.0
LT	723+98.00	727+74.15	376.15	VARIABLE		300.0
LT	733+50.00	736+35.68	285.68	VARIABLE		180.0
LT	736+90.95	740+85.00	394.05	VARIABLE		302.0
RT	722+21.57	727+79.82	558.25	VARIABLE		459.0
RT	733+98.28	740+85.00	686.72	VARIABLE		530.0
LT	721+50.00	723+98.00	248.00	4.0		111.0
LT	728+18.00	729+02.75	84.75	VARIABLE		37.0
LT	732+67.25	733+50.00	82.75	VARIABLE		32.0
LT	740+85.00	744+00.00	315.00	VARIABLE		141.0
RT	728+25.00	729+88.80	163.80	VARIABLE		62.0
RT	732+03.05	733+53.00	149.95	3.0		50.0
RT	740+85.00	744+00.00	315.00	VARIABLE		141.0
TOTAL			508.0		1,771.0	574.0

* SEE TYPICAL SECTIONS AND PLANS

BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)			
LOCATION	LENGTH (FOOT)	WIDTH (FOOT)	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE) 42001430 (SQ YD)
729+02.75 TO 729+08.75	6	33.83	23.0
732+61.25 TO 732+67.25	6	33.83	23.0
TOTAL			46.0

CONCRETE GUTTER			
LOCATION	CONCRETE GUTTER TYPE A 60602500 (FOOT)	CLASS S1 CONC. (OUTLET) 60600095 (CU YD)	GUTTER REMOVAL 44000400 (FOOT)
LT	721+50.00 TO 723+62.00		212.0
LT	741+21.00 TO 744+00.00		279.0
RT	741+21.00 TO 744+00.00		279.0
LT	723+62.00 TO 724+13.36	5.2	
LT	740+69.64 TO 741+21.00	5.4	
RT	740+69.64 TO 741+21.00	5.4	
LT	721+50 TO 724+03		253.0
LT	740+36 TO 744+00		364.0
RT	740+76 TO 744+00		324.0
TOTAL			941.0

EFK Moen, LLC
Civil Engineering Design