LOCATION OF WORK:	FAP 711 (IL 119)	S.N. 092-0207
	RURAL TWO LANE	RURAL TWO LANE
	MINOR ARTERIAL	MINOR ARTERIAL
	STA. 721+50 TO STA. 744+00	STA. 729+38.75 TO STA. 732+31.25
	VERMILION COUNTY	VERMILION COUNTY
FUNDING BREAKOUT:	80% FEDERAL, 20% STATE	80% FEDERAL, 20% STATE
CONSTRUCTION TYPE CODE:	0004	0011

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1.0	0.0	1.0
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1.0	0.0	1.0
50300100	FLOOR DRAINS	EACH	34.0	0.0	34.0
50300225	CONCRETE STRUCTURES	CU YD	301.2	0.0	301.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	505.3	0.0	505.3
50300260	BRIDGE DECK GROOVING	SQ YD	1,178.0	0.0	1,178.0
50300265	SEAL COAT CONCRETE	CU YD	62.2	0.0	62.2
50300280	CONCRETE ENCASEMENT	CU YD	4.2	0.0	4.2
50300300	PROTECTIVE COAT	SQ YD	1,531.0	0.0	1,531.0
50401005	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 48 IN.	FOOT	1,728.0	0.0	1,728.0
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	147,770.0	0.0	147,770.0
50800515	BAR SPLICERS	EACH	1,337.0	0.0	1,337.0
51201600	FURNISHING STEEL PILES HP12X53	FOOT	550.0	0.0	550.0
51201900	FURNISHING STEEL PILES HP14X89	FOOT	1,449.0	0.0	1,449.0

• DENOTES SPECIALTY ITEM

14

EFK·Moen, LLC
Civil Engineering Design

FILE NAME = o:\pw_work\pwidot\deterslj\d2373920\D3-06-0570614-sht-S00.dgn	USER NAME = deterslj	DESIGNED - JRD	REVISED - BJH 01/08/2014
		DRAWN - MSK	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED - SLD	REVISED -
	PLOT DATE = 1/13/2014	DATE - 10/18/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: N.A. | SHEET NO. 3 OF 8 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
711	116BR-1	VERMILION	84	5
		CONTRACT NO. 70614		
	ILLINOIS FED. AID PROJECT			