

LOCATION OF WORK:

FAP 711 (IL 119) S. N. 092-0207
 RURAL TWO LANE RURAL TWO LANE
 MINOR ARTERIAL MINOR ARTERIAL
 STA. 721+50 TO STA. 744+00 STA. 729+38.75 TO STA. 732+31.25
 VERMILION COUNTY VERMILION COUNTY

FUNDING BREAKOUT:
 CONSTRUCTION TYPE CODE:

80% FEDERAL, 20% STATE 80% FEDERAL, 20% STATE
 0004 0011

CODE NO.	ITEM	UNIT	TOTAL QUANTITY		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	20.0	10.0	10.0
67100100	MOBILIZATION	L SUM	1.0	0.5	0.5
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1.0	1.0	0.0
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	1.0	0.0
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1.0	1.0	0.0
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.0	0.0	1.0
70300100	SHORT TERM PAVEMENT MARKING	FOOT	100.0	100.0	0.0
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	1,215.0	1,215.0	0.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	435.0	435.0	0.0
70400100	TEMPORARY CONCRETE BARRIER	FOOT	487.5	487.5	0.0
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	487.5	487.5	0.0
70600250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0	0.0
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	2.0	2.0	0.0
• 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4,400.0	4,400.0	0.0

• DENOTES SPECIALTY ITEM

14

EFK•Moen, LLC
 Civil Engineering Design

FILE NAME =	USER NAME = hoganbj	DESIGNED - JRD	REVISED - BJH 01/24/2014	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RATE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
o:\pwork\p\idat\hoganbj\d8373989\83-0578614-eh-500.dgn	DRAWN - MSK	REVISED -	711			1168R-1	VERMILION	84	7	
PLOT SCALE = 40,0000 1/2 in.	CHECKED - SLD	REVISED -	CONTRACT NO. 70614							
PLOT DATE = 1/24/2014	DATE - 10/18/13	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: N.A. SHEET NO. 5 OF 8 SHEETS						