

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE												
				MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	HPR, TURN LANE AND BICYCLE LANE ON ARCHER	ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)		
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	80% FED 20% CITY	100% CITY	100% CITY	100% CITY		
28000500	INLET AND PIPE PROTECTION	EACH	162.0	162.0												
28100705	STONE DUMPED RIPRAP, CLASS A3	SQ YD	1293.0	1293.0												
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	643.0	643.0												
28200200	FILTER FABRIC	SQ YD	1936.0	1936.0												
31100700	SUBBASE GRANULAR MATERIAL, TYPE A 8"	SQ YD	82194.0	71400.0						9895.0		812.0			87.0	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	433.0	433.0												
35501312	HOT-MIX ASPHALT BASE COURSE, 7"	SQ YD	17964.0	8620.0						8536.0		721.0			87.0	
35501318	HOT-MIX ASPHALT BASE COURSE, 8 1/2"	SQ YD	44375.0	44375.0												
35650200	BASE COURSE WIDENING 7"	SQ YD	368.0	339.0								29.0				
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1800.0	1500.0						300.0						
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	126.0	117.0						8.0		1.0			0.0	
40600300	AGGREGATE (PRIME COAT)	TON	659.0	613.0						41.0		4.0			1.0	
40600837	POLYMERIZED LEVELING BINDER (MACHINE METHOD), N70	TON	13437.0	13437.0												
40600895	CONSTRUCTING TEST STRIP	EACH	3.0	3.0												

FILE NAME:
 USER NAME: sparksg
 DESIGNED - AWM
 DRAWN - TJD
 CHECKED - AWM
 DATE - 12/04/2013
 PLOT SCALE: 100.0000
 PLOT DATE: Feb-04-2014 09:00:44PM

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
 SUMMARY OF QUANTITIES
 SCALE: N/A SHEET 2 OF 24 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21W-3, T5-1, R5-71	SANGAMON	679	5
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72890	

REV. 4-15-14