STORM SEWER SCHEDULE (CONTINUED FROM PREVIOUS SHEET)

STATION	OFFSET	SIDE	TYPE	STANDARD AND DESIGN NUMBER	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 60"	PRC FLARED DROP BOX END SECTIONS ERS, ELLIPTICAL WITH GRATE 42"	PRC FLARED DROP BOX END SECTIONS ERS, ELLIPTICAL WITH GRATE 48"	METAL END SECTIONS 12"	PIPE DRAINS 12"	MANHOLES, TYPE A 4' A-1-C	4' A-3	4' A-3V	4' A-8	4' A-10	5' A-1-C	5' A-3V	5' A-8	5' MEDIAN INLET (604106)	6' A-1-C	6' A-1-C SPL	6' A-3V	6' A-8	7' A-1-C	7' A-3V	7' A-8	8' A-3V	8' A-1-C	9' A-3V	9' MEDIAN INLET (604106)	SPECIAL	INLETS TYPE A A-3	TYPE A A-3V	TYPE A A-8	TYPE A A-10	TYPE B B-1-C	TYPE B B-3V	TYPE B B-8	TYPE B B-10	TYPE B MEDIAN INLET (604106)	TYPE E SPECIAL 4'x4'	INLET BOX TYPE E STD 610001	STORM SEWERS, CLASS A, TYPE 2 60"	STORM SEWER (WATER MAIN REQUIREMENTS) 12"	15"	18"	24"	30"	36"	42"	48"	60"	ERS ELLIPTICAL 24"	ERS ELLIPTICAL 48"	TRENCH BACKFILL
					EACH							FOOT	EACH																																FOOT												CU YD
12+40.00	23.50'	RT	INLET																																								1														
			SS																																											88											12
14+23.77	38.62	LT	INLET																																								1														
			SS																																											44											6
13+79.56	41.97'	LT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																											77											16
13+64.75	33.56'	RT	MH	602401, 602601, 602701, 604001														1																																							
14+76.85	23.50'	RT	END SECTION	542301	1																																																			
			SS																																											18											1
14+58.34	23.50'	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																											88											16
MEADOWBROOK RD																																																									
63+66.61	42.03'	LT	MH	602401, 602601, 602701, 604001									1																																												
			SS																																											4											
63+69.25	33.32'	LT	INLET																																								1														
			SS																																											48											7
63+69.58	18.44'	RT	INLET																																								1														
MERCANTILE DR																																																									
5+72.98	35.50'	RT	MH	602401, 602601, 602701, 604001									1																																												
			SS																																													228									64
8+00.50	35.50'	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																												4										1
STADIUM DR																																																									
10+48.42	27.62'	LT	MH	602406, 602701,																				1																																	
			SS																																																28						5
10+80.00	19.50'	LT	INLET																																								1														
10+63.33	38.36'	RT	MH	602401, 602601, 602701, 604036												1																																									
			SS																																											22											3
10+80.00	19.50'	RT	INLET																																								1														
			SS																																												40										8
			SS																																																38						10
11+20.86	24.58'	LT	MH	602406, 602701,																		1																																			
HOLLIS DR																																																									
9+82.00	18.00'	RT	MH	602401, 602601, 602701, 604011											1																																										
			SS																																												34										5
9+82.00	18.00'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																														116								38
11+00.00	18.00'	LT	MH	602401, 602601, 602701, 604011															1																																						
11+00.00	38.50'	LT	INLET	602301, 604006																														1																							
			SS																																											20											3
11+00.00	18.00'	RT	INLET	602301, 604011																															1																						
			SS																																											36											5
			SS																																															94							62
11+95.00	18.00'	LT	MH	602401, 602701, 604011															1																																						
			SS																																															98							80
13+00.00	18.00'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																															36							37
13+00.00	18.00'	RT	MH	602406, 602701,																				1																																	
			SS																																															176							215
14+79.51	18.00'	RT	MH	602411, 602701, 604011																							1																														
			SS																																																	32					43
14+69.31	18.00'	LT	MH	602406, 602601,																				1																																	
			SS																																																	22					24
14+68.98	39.38'	LT	DROP BOX						1																																																
14+84.25	40.38'	LT	END SECTION	542301			1																																																		
			SS																																														22								27
14+84.25	18.00'	LT	MH	602401, 602601, 602701, 604011															1																																						
			SS																																														62								53

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\edwardsjd\d0373645\0072890-sht-schedule.dgn
Default
USER NAME = edwardsjd
PLOT SCALE = 100.0000 ' / in.
PLOT DATE = Apr-08-2014 03:06:29PM
DESIGNED - JMO
DRAWN - JMO
CHECKED - AWM
DATE - 12/4/2013
REVISED - JDE 4/8/2014
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SCHEDULE OF QUANTITIES

SCALE: | SHEET 16 OF 27 SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	79

CONTRACT NO. 72890

ILLINOIS FED. AID PROJECT

1 REV. 4-15-14