

PIPE CULVERTS

STATION TO STATION	SIDE	STANDARD AND DESIGN NUMBER	PIPE CULVERTS														TRENCH BACKFILL
			PRECAST REINFORCED CONCRETE FLARED END SECTION				METAL END SECTIONS		PIPE CULVERTS						CU YD		
			18"	24"	30"	36"	15"	18"	CLASS A			CLASS D					
									TYPE I								
18"	24"	30"	36"	15"	18"	15"	18"	24"	30"	36"	15"	18"	FOOT				
MAINLINE WABASH AVENUE																	
WABASH AVE (FAU 8012)																	
344+42.20	344+94.20	RT	542401													52	8
351+29.66	351+65.66	RT	542401													36	6
358+06.08	360+93.92	RT	542301							244							30
358+06.08	360+93.92	RT	542301	2						244							30
382+50.00	383+40.00	LT	542301		2					90							19
382+50.00	383+40.00	LT	542301		2					90							19
382+62.50	383+69.00	RT	542301				2						108				25
383+82.21		LT/RT	542301										136				CLSM
383+82.21		LT/RT	542301										136				CLSM
BUNKER HILL ROAD																	
2+76.65	3+25.44	LT	542401				2			54							
3+92.60	4+07.30	LT/RT	542301		2							58					11
4+16.81	4+80.60	RT	542401				2			56							
4+74.23	5+22.73	LT	542401				2			56							
SUBTOTAL				4	6	4	2	6	4	166	488	238	272	108	0	88	148
HOLLIS - EAST LIMITS TO STA 9+75 & COCKRELL LN																	
COCKRELL LN																	
12+67.30	13+08.00	LT	542401				2									42	1
15+52.81	15+94.10	LT	542301				2									42	4
SUBTOTAL				0	0	0	0	4	0	0	0	0	0	0	84	0	5
TOTAL				4	6	4	2	10	4	166	488	238	272	108	84	88	153

*NOTE: SEE PIPE CULVERT SCHEDULE FOR MORE 24" END SECTIONS.

FRAMES AND LIDS TO BE ADJUSTED

STATION	SIDE	OFFSET	60300605		
			FRAMES AND LIDS TO BE ADJUSTED		
			WATER VALVE VAULTS	WATER METER VAULTS	SANITARY SEWER MANHOLES
EACH					
MAINLINE WABASH AVENUE					
WABASH AVE (FAU 8012)					
358+98.4	LT	84.1			
359+01.5	LT	80.9			
359+10.8	LT	87.4			
391+26.9	RT	82.8			
411+35.8	RT	56.7			
412+46.3	LT	59.7			
413+67.9	RT	62.1			
415+49.8	LT	35.0			
416+93.3	RT	61.1			
418+50.4	LT	69.7			
418+95.2	LT	70.6			
419+04.8	RT	64.9			
419+33.9	LT	64.8			
419+83.8	RT	62.5			
424+51.9	RT	60.9			
424+56.7	RT	62.0			
426+28.4	LT	71.0			
427+14.5	LT	70.9			
429+89.8	RT	61.1			
432+97.5	RT	65.0			
434+18.6	LT	67.5			
435+74.6	RT	70.0			
438+17.9	LT	68.1			
438+18.0	RT	72.0			
438+35.9	RT	67.4			
439+00.3	RT	64.6			
442+19.0	LT	69.7			
453+24.7	RT	67.2			
453+29.7	LT	72.0			
454+00.9	LT	72.6			
454+44.2	RT	51.9			
466+92.2	LT	53.9			
466+92.6	LT	62.0			
466+93.0	LT	64.4			
467+18.1	LT	68.7			
467+19.8	RT	60.3			
470+18.0	RT	67.2			
472+89.0	RT	64.5			
475+40.8	RT	47.9			
475+87.6	RT	63.5			
482+23.6	RT	72.0			
482+26.1	RT	80.7			
482+35.9	LT	39.7			
482+77.7	RT	77.2			
483+38.0	LT	29.8			
ARCHER ELEVATOR RD					
13+78.3	RT	59.8			
MERCANTILE DR					
8+27.9	LT	49.8			
STADIUM DR					
10+68.9	RT	26.5			
SUBTOTAL			24	6	18
USE				48	
HOLLIS - EAST LIMITS TO STA 9+75 & COCKRELL LN					
HOLLIS DR					
0+11.3	RT	28.2			
0+21.2	RT	28.5			
0+23.0	RT	35.0			
0+29.5	LT	31.9			
4+92.7	LT	36.4			
5+75.0	RT	25.9			
7+49.7	LT	36.4			
7+78.1	LT	23.7			
9+51.6	LT	31.8			
COCKRELL LN					
13+22.1	LT	25.0			
13+24.9	RT	43.8			
13+98.8	RT	43.0			
16+14.2	LT	24.6			
16+32.2	LT	10.0			
16+37.3	RT	44.3			
SUBTOTAL			6	7	2
USE				15	
TOTAL				63	

INLETS TO BE ADJUSTED

STATION	SIDE	OFFSET	60260100	
			INLETS TO BE ADJUSTED	EACH
MAINLINE WABASH AVENUE				
WABASH AVE (FAU 8012)				
408+49.92	RT	91.98		1
KOKE MILL				
20+81.05	LT	32.96		1
2+90.27	LT	33.25		1
TOTAL				3

PIPE UNDERDRAIN

STATION TO STATION	SIDE	60100060 60107600 60108100			
		CONCRETE HEADWALLS FOR PIPE DRAINS	PIPE UNDERDRAIN 4"	PIPE UNDERDRAIN 4" (SPECIAL)	
		EACH	FOOT		
MAINLINE WABASH AVENUE					
RAMP A					
13+36.9	15+50.0	RT	1	212.5	30.0
13+36.9	15+50.0	LT	1	216.5	26.0
15+50.0	18+38.5	RT		287.9	
15+50.0	19+25.6	LT		377.8	
RAMP C					
11+11.5	15+80.3	LT	2	469.2	26.0
TOTAL			4	1,563.9	82.0
USE			4	1,564	82

RELATED ITEM (SEE SCHEDULE FOR MORE INFORMATION)		20800150
		TRENCH BACKFILL
		CU YD
MAINLINE WABASH AVENUE		
PIPE CULVERT REMOVAL & FILLING EXISTING CULVERT	657	
PIPE CULVERTS (TEMPORARY)	19	
PIPE CULVERTS	148	
STORM SEWERS	7981	
SANITARY SEWER	131	
SUBTOTAL	8936	
HOLLIS - EAST LIMITS TO STA 9+75 & COCKRELL LN		
PIPE CULVERT REMOVAL & FILLING EXISTING CULVERT	28	
PIPE CULVERTS	5	
STORM SEWERS	277	
SUBTOTAL	310	
TOTAL	9246	

STATION TO STATION		SIDE	20015802
			PLUG EXISTING DECK DRAINS
			FOOT
MAINLINE WABASH AVENUE			
1-72			
368+25	371+72	LT/RT	40
TOTAL			40

SANITARY SEWER SCHEDULE			
STATION	20057000		20800150
	SANITARY SEWER, 10"	FOOT	TRENCH BACKFILL
		CU YD	
MAINLINE WABASH AVENUE			
BUNKER HILL ROAD			
8+73.2	190.0	130.9	
TOTAL	190.0	130.9	
USE	190	131	

FILE NAME =	USER NAME = edwardsjd	DESIGNED - JMO	REVISED - JDE 2/21/2014
c:\pwworksp\edwardsjd\0373645106	2010-01-28-14:00:00.dgn	DRAWN - JMO	REVISED - JDE 4/8/2014
Default	PLOT SCALE = 100.0000' / 1"	CHECKED - AMM	REVISED -
	PLOT DATE = Apr-09-2014 09:06:00PM	DATE - 12/4/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SCHEDULE OF QUANTITIES
SCALE: SHEET 19 OF 27 SHEETS STA. TO STA.

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	82
CONTRACT NO. 72890			ILLINOIS FED. AID PROJECT	

REV. 4-15-14