STORM SEWER SCHEDULE (CONTINUED FROM PREVIOUS SHEET)

STATION	OFFSET	SIDE	TYPE	STANDARD AND DESIGN NUMBER	PRECAST REINFORCED CONCRETE FLARED END SECTIONS				PRC FLARED DROP BOX END SECTIONS ERS, ELLIPTICAL WITH GRATE		METAL END SECTIONS	PIPE DRAINS	MANHOLES, TYPE A																						INLETS										INLET BOX TYPE E STD 610001	STORM SEWERS, CLASS A, TYPE 2 60"	STORM SEWER (WATER MAIN REQUIREMENTS)										TRENCH BACKFILL
													4'					5'				6'				7'				8'		9'			TYPE A				TYPE B				TYPE E														
													A-1-C	A-3	A-3V	A-8	A-10	A-1-C	A-3V	A-8	MEDIAN INLET (604106)	A-1-C	A-1-C SPL	A-3V	A-8	A-1-C	A-3V	A-8	A-3V	A-1-C	A-3V	MEDIAN INLET (604106)	SPECIAL	A-3	A-3V	A-8	A-10	B-1-C	B-3V	B-8	B-10	MEDIAN INLET (604106)	SPECIAL 4'x4'			12"	15"	18"	24"	30"	36"	42"	48"	60"	ERS ELLIPTICAL 24"	ERS ELLIPTICAL 48"	
					12"	15"	24"	60"	42"	48"	12"	12"																																											
					EACH							FOOT	EACH																																FOOT										CU YD
15+50.00	18.00'	LT	MH	602401, 602601, 602701, 604011															1																																				
15+96.00	23.00'	RT	MH	602401, 602601, 602701, 604001									1																																										
			SS																																										46										16
15+50.00	18.00'	RT	INLET	602306, 604011																																			1																
			SS																																										36										13
			SS																																													116							112
16+65.64	18.00'	LT	INLET																																								1												
16+65.64	18.00'	RT	INLET																																								1												
			SS																																												32							4
			SS																																												84							28
17+50.00	18.00'	LT	MH	602401, 602601, 602701, 604011											1																																								
17+50.00	18.83'	RT	INLET	602301, 604011																															1																				
			SS																																										37										5
			SS																																												75							25
18+25.00	21.00'	LT	MH	602401, 602601, 602701, 604001									1																																										
			SS																																												75							23
19+00.00	19.27'	LT	MH	602401, 602601, 602701, 604011											1																																								
19+00.00	21.27'	RT	INLET	602301, 604011																															1																				
			SS																																										41										5
			SS																																												68							24
KOKE MILL RD																																																						
			SS																																															110				121
24+03.00	54.00'	LT	MH	602411, 602701, 604001																						1																													
24+12.24	33.48'	LT	INLET	602306, 604001																																			1																
			SS																																										10										1
24+12.24	44.50'	LT	MH	602401, 602701, 604006										1																																									
			SS																																										8										1
24+02.00	44.50'	LT	MH	602401, 602601, 602701, 604006										1																																									
			SS																																											8										3
			SS																																														456						320
SUBTOTAL					1	2	4	1	1	1	1	16	8	3	10	9	0	5	12	8	2	1	0	3	1	8	4	1	1	4	1	2	1	4	5	25	0	2	3	2	0	1	15	1	990	2,558	1,841	2,394	2,628	1,364	504	54	3,324	462	62	32	7,977
HOLLIS - EAST LIMITS TO STA 9+75 & COCKRELL LN																																																						
HOLLIS DR																																																						
26+56.08	48.76'	LT	END SECTION	542301			1																																															
			SS																																													20							2
26+58.66	22.66'	LT	MH	602406, 602701,																			1																																
0+08.19	23.02'	RT	MH	602401, 602601, 602701, 604001									1																																										
			SS																																												38							10
0+50.00	19.90'	RT	MH	602401, 602601, 602701, 604046													1																																						
0+50.00	36.15'	RT	INLET	602301, 604036																																1																			
			SS																																										12										2
			SS																																												86							9
1+37.00	19.67'	RT	INLET	602306, 602601,																																			1																
			SS																																										82										11
2+21.00	19.50'	RT	INLET	602306, 602601,																																			1																
			SS																																										88										12
3+11.00	19.50'	RT	INLET	602306, 602601,																																			1																
			SS																																										88										12
4+01.00	19.50'	RT	INLET	602301, 604011																															1																				
0+17.51	24.90'	LT	MH	602401, 602601, 602701, 604001									1																																									
			SS																																												64							8
0+85.00	19.20'	LT	MH	602401, 602601, 602701, 604011															1																																				
			SS																																												82							10

CONTINUED ON NEXT SHEET