

CONCRETE CURB & GUTTER

STATION TO STATION	SIDE	60600095	60602800	60603800	60604400	60605000	X6060048	X6060052	X6061005
		CLASS SI CONCRETE (OUTLET)	CONCRETE GUTTER, TY B	COMBINATION CONCRETE CURB AND GUTTER					CONCRETE CURB, TY B (SPECIAL)
				TY B-6.12	TY B-6.18	TY B-6.24	TY B-6.18 (SPECIAL)	TY B-6.24 (SPECIAL)	
		CU YD	FOOT						
MAINLINE WABASH AVENUE									
WABASH AVE (FAU 8012)									
358+14.2	8+33.7 (INTERNATIONAL DR)	LT				190.4			
8+35.3 (INTERNATIONAL DR)	361+09.8	LT				198.4			
372+15.0	376+23.5	LT				408.5			
374+10.0	378+47.9	RT	3.21			438.7			
389+59.2	8+31.5 (BUNKER HILL RD)	LT				233.2			
390+37.8	11+93.4 (ASH GROVE)	RT				198.0			
8+71.0 (BUNKER HILL RD)	392+62.1	LT				110.0			
11+66.6 (ASH GROVE)	392+64.8	RT				173.9			
408+14.7	408+51.8	RT		64.4					
408+33.5	408+52.5	LT		28.2					
408+91.9	409+15.9	RT		43.2					
408+95.4	409+14.4	LT		28.2					
415+55.4	10+75.0 (HAMLIN PKWY)	LT				78.9			
11+26.8 (HAMLIN PKWY)	417+20.6	LT				103.2			
417+07.8	418+93.5	LT					188.7		
417+20.6	421+05.4	LT				385.0			
425+59.6	10+91.8 (ARCHER ELEVATOR RD)	LT				95.9			
425+91.5	10+76.2 (ARCHER ELEVATOR RD)	LT		21.9					
11+42.2 (ARCHER ELEVATOR RD)	427+49.0	LT				125.3			
427+49.0	431+84.0	LT				435.3			
429+89.1	431+88.5	RT				199.5			
431+88.5	9+07.1 (PLEASANT RUN)	RT				67.6			
9+07.1 (PLEASANT RUN)	433+43.5	RT				84.5			
434+96.0	435+75.4	RT					79.4		
435+75.4	437+25.5	RT				150.2			
437+25.5	63+35.2 (S MEADOWBROOK RD)	RT				185.0			
437+34.9	11+64.3 (N MEADOWBROOK RD)	LT				188.3			
63+35.2 (S MEADOWBROOK RD)	439+78.7	RT				173.7			
11+86.0 (N MEADOWBROOK RD)	439+87.9	LT				187.9			
439+33.5	442+35.0	LT	320.7						
439+87.9	441+72.9	LT				185.1			
441+72.9	442+35.0	LT					62.1		
447+42.6	452+19.7	RT				477.5			
452+05.5	11+62.2 (N MERCANTILE DR)	LT				193.1			
452+19.7	8+09.9 (S MERCANTILE DR)	RT				195.3			
8+59.3 (S MERCANTILE DR)	454+48.6	RT				136.3			
12+23.0 (N MERCANTILE DR)	454+60.1	LT				217.8			
454+60.1	459+36.5	LT				470.7			
463+85.6	11+23.8 (HAPPY LANDING)	LT				138.4			
11+75.8 (HAPPY LANDING)	466+38.2	LT				192.0			
466+38.2	468+59.1	LT				218.4			
470+45.6	470+59.6	RT					37.2		
470+84.7	470+98.9	RT					37.2		
478+26.0	482+47.7	RT				427.2			
478+91.2	479+42.0	RT		53.4					
482+47.7	21+07.0 (KOKE MILL RD)	RT				71.3			
483+08.7	23+49.7 (KOKE MILL RD)	LT				96.9			

CONTINUED ON NEXT SHEET

CONCRETE CURB & GUTTER (CONTINUED)

STATION TO STATION	SIDE	60600095	60602800	60603800	60604400	60605000	X6060048	X6060052	X6061005	
		CLASS SI CONCRETE (OUTLET)	CONCRETE GUTTER, TY B	COMBINATION CONCRETE CURB AND GUTTER					CONCRETE CURB, TY B (SPECIAL)	
				TY B-6.12	TY B-6.18	TY B-6.24	TY B-6.18 (SPECIAL)	TY B-6.24 (SPECIAL)		
		CU YD	FOOT							
INTERNATIONAL PKWY										
7+84.4	8+35.3	LT				50.9				
BUNKER HILL RD										
7+98.4	8+71.0	LT				73.2				
HAMLIN PKWY										
10+58.7	10+75.0	RT			16.3					
10+58.8	10+75.0	RT			16.2					
10+94.5	11+38.3	LT			43.7					
ARCHER ELEVATOR RD										
10+91.8	11+01.8	LT				10.0				
11+01.8	9+57.6 (HPR DR)	LT			308.8					
11+42.2	11+65.4	RT			23.2					
11+65.4	10+83.3 (YUCAN DR)	RT			240.1					
9+57.6 (HPR DR)	14+66.9	LT			77.7					
10+83.3 (YUCAN DR)	14+66.9	RT			71.4					
PLEASANT RUN										
9+07.0	9+42.7	LT			35.7					
9+07.1	9+42.9	RT			35.8					
S MERCANTILE DR										
5+23.3	19+36.4 (HOLLIS DR)	RT			57.9					
5+28.7	10+75.3 (STADIUM DR)	LT			70.7					
10+80.1 (STADIUM DR)	6+59.1	LT			76.3					
19+16.0 (HOLLIS DR)	6+61.1	RT			78.5					
6+61.1	8+59.3	RT			198.2					
STADIUM DR										
10+75.3	12+09.8	LT			153.2					
11+91.0	12+42.7	LT			54.1					
10+80.1	12+60.1	RT			172.7					
HOLLIS DR										
9+75.0	19+16.0	RT			941.2					
9+75.0	19+36.4	LT			961.2					
10+33.9	11+82.0	LT				148.1				
KOKE MILL RD										
20+75.4	21+07.0	LT			30.3					
23+49.7	27+68.2	LT			430.3					
SUBTOTAL			3.21	320.70	387.00	3997.00	7588.70	336.80	141.50	0.00
USE			3.3	321	387	3,997	7,589	337	142	0
HOLLIS EAST LIMITS TO 9+75 & COCKRELL										
HOLLIS DR										
0+00.0	9+75.0	RT			976.4					
0+00.0	18+65.3 (COCKRELL LN)	LT			571.8					
18+65.3 (COCKRELL LN)	7+75.1	LT			279.1					
7+75.1	8+96.8	LT				122.2				
8+96.8	9+75.0	LT			78.2					
9+00.0	9+27.9	RT							27.9	
COCKRELL LN										
12+23.3	18+65.3	LT			642.1					
13+41.7	18+65.3	RT			499.0					
SUBTOTAL			0.0	0.0	0.0	3046.6	0.0	122.2	0.0	27.9
USE			0	0	0	3,047	0	123	0	28
TOTAL			3.3	321	387	7,044	7,589	460	142	28

FILE NAME =	USER NAME = edwardsjd	DESIGNED - JMO	REVISED - JDE 2/21/2014
es:\pwork\pwork\edwardsjd\0373645\0672890-sh-t-schedule.dgn		DRAWN - JMO	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED - AWM	REVISED -
	PLOT DATE = Feb-21-2014 02:21:52PM	DATE - 12/4/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAU ROUTE 8012 (WABASH AVE)
SCHEDULE OF QUANTITIES

SCALE: SHEET 20 OF 27 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	83
CONTRACT NO. 72890			ILLINOIS FED. AID PROJECT	