CURVE 1733
P.I. STA= 467+86.01
Δ= 44° 53' 39" (LT)
D= 1° 30' 01"
R= 3,818.77'
T= 1,577.66'
L= 2,992.20'
E= 313.06'
e= 2.3%
T.R. ATTAINED = 84.0'
S.E. RUN ATTAINED = 96.6'
T.R. REMOVED = 69.8'
S.E. RUN REMOVED = 80.2'
P.C. STA= 452+08.36
P.T. STA= 482+00.56
S.E. ATTAINED STA 450+59.64 TO STA 452+40.24
S.E. REMOVED STA 481+40.39 TO STA 482+90.39

HALEY, L.L.C.
PARCEL NO. 6134135

FIRST UNITED METHODIST CHURCH
PARCEL NO. 6134150

THE REAL ESTATE GROUP, L.L.C.
PARCEL NO. 6134134

TOWN & COUNTRY BANK

EXISTING ROW LINE

LIMIT OF CONSTRUCTION (TYP.)

STA 11+67.06
38.84' RT

STA 11+18.36
37.16' LT

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

2 CENTERED CURVE
60' - 300'
OFFSET = 12.00'

STA 10+87.00
56.23' LT

STA 464+00.00
60.00' LT

PROPOSED ROW LINE

STA 464+42.14
52.13' LT

STA 10+87.00
61.50' RT

TOWN & COUNTRY BANK COMPLEX

2 CENTERED CURVE
110' - 215'
OFFSET = 5.00'

STA 466+07.00
71.00' LT

STA 466+15.00
76.00' LT

STA 466+50.00
76.00' LT

STA 466+38.15
48.00' LT

PROPOSED TEMPORARY EASEMENT

PROPOSED COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.24

PROPOSED HOT-MIX ASPHALT SHOULDER, 8"

EXISTING LIGHT TO BE UNDISTURBED

PROPOSED PORTLAND CEMENT CONCRETE SIDEWALK, 4"

PROPOSED ℄ WABASH AVENUE (FAU 8012)

STA 468+25.62
48.00' LT

STA 469+65.00
75.00' LT

STA 469+65.00
71.00' LT

300' TAPER

STA 468+59.08
45.99' LT

MATCH LINE STATION 464+00.00

MATCH LINE STATION 470+00.00

82°01'21"
LOC TAN

PIPE CULVERT REMOVAL, 15"x187.1'

STA 465+00

STA 465+19.28 (FAU 8012/WABASH AVE)
= STA 10+00.00 (HAPPY LANDING DR)

STA 467+28.26
62.00' RT

STA 467+34.00
60.00' RT

STA 466+65.00
60.00' RT

PROPOSED PORTLAND CEMENT CONCRETE SIDEWALK, 4"

EXISTING SIGN ON THIS PARCEL IS NOT TO BE DISTURBED.

STA 464+83.64
60.00' RT

STA 464+84.45
65.37' RT

+37.8 CE

STA 466+74.00
81.00' RT

PROPOSED TEMPORARY EASEMENT

24.0'

+91.5 CE

STA 467+04.00
81.00' RT

STA 467+10.00
60.00' RT

PROPOSED ROW LINE

STA 467+24.00
62.00' RT

STA 467+24.00
73.00' RT

BM 72

STA 467+34.00
62.00' RT

STA 467+34.00
73.00' RT

PROPOSED PERMANENT EASEMENT

LEATH FURNITURE

35.0'

+65.7 CE

STA 467+95.00
80.00' RT

STA 467+88.00
88.00' RT

STA 467+48.00
88.00' RT

LIMIT OF CONSTRUCTION (TYP.)

PROPOSED HOT-MIX ASPHALT SHOULDER, 8"

POOL CENTER INC.

HOUSE TO A HOME
EDWARD E. OSMAN
& DIANE OSMAN
PARCEL NO. 6134140

CAPITOL REAL ESTATE PROPERTIES, L.L.C. 1
PARCEL NO. 6134141

SAMUEL MUSIC

DLIC-SPRINGFIELD HOLDING COMPANY, L.L.C.
PARCEL NO. 6134142

BM 72 - CHIS. "□" IN N. EDGE OF LIGHT POLE FOUNDATION,
S. SIDE WABASH AVE. BETWEEN LEATH FURNITURE & SAMUEL MUSIC
N 1125682.882 E 2422190.504
STA 467+28.70, 113.4' RT
ELEV. 609.86

N

20' 0' 20'
GRAPHIC SCALE IN FEET

FILE NAME = c:\pw_work\pwidot\sparksgw\d0373645\D672890-sht-plan-Wabash24.dgn	USER NAME = sparksgw	DESIGNED - AWM	REVISED -
		DRAWN - JCW	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED - AWM	REVISED -
	PLOT DATE = Feb-04-2014 01:35:11PM	DATE - 12/04/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WABASH AVENUE
PLAN VIEW

SCALE: 1:20 | SHEET NO. OF SHEETS | STA. 464+00.00 TO STA. 470+00.00

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	165
		CONTRACT NO. 72890		
	ILLINOIS FED. AID PROJECT			