

LIGHTING REMOVAL ITEMS

STATION	SIDE	84200500	84200804	84500110	84500120	84500130
		REMOVAL OF LIGHTING UNIT, SALVAGE	REMOVAL OF POLE FOUNDATION	REMOVAL OF LIGHTING CONTROLLER	REMOVAL OF ELECTRIC SERVICE INSTALLATION	REMOVAL OF LIGHTING CONTROLLER FOUNDATION
EACH						
SIGNALS & LIGHTING AT I-72 RAMPS						
WABASH AVE						
355+54	37' RT	1	1			
366+40	RT			1	1	1
366+50	65' LT	1	1			
367+98	37' RT	1	1			
382+19	47' LT	1	1			
383+56	65' RT	1	1			
387+33	40' LT	1	1			
395+00	LT	TO BE REMOVED BY OTHERS				
438+20	LT	TO BE REMOVED BY OTHERS				
453+00	LT	TO BE REMOVED BY OTHERS				
465+75	LT	TO BE REMOVED BY OTHERS				
RAMP C						
1+75	20' RT	1	1			
3+50	20' RT	1	1			
RAMP D						
17+66	20' RT	1	1			
RAMP A						
0+00	17' RT	1	1			
5+50	17' RT	1	1			
8+50	17' RT	1	1			
TOTAL		12	12	1	1	1

PROPOSED LIGHTING ITEMS

STATION	SIDE	80400100	82102250	82102400	82500300	82500330	83003600	83004600	83600355	83600357	83800650
		ELECTRIC SERVICE INSTALLATION	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	LIGHT POLE, ALUMINUM, 50 FT. M.H., 15 FT. DAVIT ARM	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN
EACH											
SIGNALS & LIGHTING AT I-72 RAMPS											
WABASH AVE											
355+54	RT		1				1		1		4
366+50	RT	1				1					
387+34	LT		1				1		1		4
RAMP C											
1+00	RT		1				1		1		4
2+70	RT		1				1		1		4
4+40	RT		1				1		1		4
RAMP D											
17+64	RT			1				1		1	4
RAMP A											
1+00	RT		1				1		1		4
2+70	RT		1				1		1		4
4+40	RT		1				1		1		4
18+75	RT	1					1				
RAMP B											
20+74	RT			1				1		1	4
SUBTOTAL		2	8	2	0	2	8	2	8	2	40
LIGHTING AT PLEASANT RUN											
WABASH AVE											
432+63	LT		1				1		1		4
433+98	RT	1			1						
SUBTOTAL		1	1	0	1	0	1	0	1	0	4
TOTAL		3	9	2	1	2	9	2	9	2	44

WIRING ITEMS

STATION TO STATION	81028760	81603000
	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	UNIT DUCT, 600V, 2 *1C NO.8, 1/C NO.8 GROUND, (XLP *TYPE USE), 3/4" DIA. POLYETHYLENE
	FOOT	FOOT
SIGNALS & LIGHTING AT I-72 RAMPS		
WABASH 354+00 RT   WABASH 366+50 RT	56	1356
WABASH 366+50 RT   RAMP D 17+66 RT		61
WABASH 366+50 RT   RAMP C 1+00 RT	108	1683
RAMP A 18+75 RT   RAMP B 20+74 RT	114	218
RAMP B 20+74 RT   WABASH 387+34 LT		409
RAMP A 18+75 RT   RAMP A 1+00 RT		1779
ADDITIONAL WIRING FOR LIGHT		80
SUBTOTAL	278	5586
LIGHTING AT PLEASANT RUN		
WABASH 433+98 RT   WABASH 432+63 LT	80	237
ADDITIONAL WIRING FOR LIGHT		5
SUBTOTAL	80	242
TOTAL	358	5,828