150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

620
615
610

EX ROW

1:10 612.70 1:9.7 1:16 -1.00% 3.57% 615.98 -3.57% 1:16 1:10.4 EX ROW PROPOSED ROW

ELEV. 610.90 ELEV. 610.99
EXISTING
2 - 24" RCP's

C=29.9 F=103.8

ELEV. 610.56 ELEV. 610.57
EXISTING
2 - 15" RCP's

392+50.00

620
615
610

EX ROW

-1.0% 2.38% 2.38% EX ROW PROPOSED ROW

ELEV. 611.03 ELEV. 611.12
EXISTING
2 - 24" RCP's

C=74.9 F=15.4

ELEV. 610.69 ELEV. 610.71
EXISTING
2 - 15" RCP's

392+00.00

615
610

EX ROW

1.19% -1.5% -2.0%

ELEV. 611.16 ELEV. 611.24
EXISTING
2 - 24" RCP's

C=29.2 F=10.5

ELEV. 610.82 ELEV. 610.84
EXISTING
2 - 15" RCP's

391+50.00

150 140 130 120 110 100 90 80 70 60 50 40 30 20 10 0 10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

FINAL SURVEY / ORIGINAL SURVEY

NO.	BY	DATE
NOTE BOOK		
AREAS		
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS CHECKED		

FILE NAME = c:\pw_work\pwidot\sparksgw\d0373645\D672890-sht-xssht-Wabash.dgn	USER NAME = sparksgw	DESIGNED - AWM	REVISED -
		DRAWN - TJD	REVISED -
	PLOT SCALE = 20.0000 ' / in.	CHECKED - AWM	REVISED -
Default	PLOT DATE = Feb-04-2014 01:51:34PM	DATE - 12/04/2013	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

WABASH AVENUE
CROSS SECTIONS

SCALE: 1"=10'H, 5'V | SHEET 36 OF 124 SHEETS | STA. 391+50.00 TO STA. 392+50.00

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
8012	21(W-3, TS-1, RS-7)	SANGAMON	679	506
		CONTRACT NO. 72890		
	ILLINOIS	FED. AID PROJECT		