

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	MAINLINE WABASH AVENUE	RETAINING WALL	SIGNALS & LIGHTING AT I-72 RAMPS	SIGNALS AT CITY STR OTHER THAN ARCHER ELEVATOR	SIGNALS AT ARCHER ELEVATOR	LIGHTING AT PLEASANT RUN	SIDEWALK	HOLLIS EAST LIMITS TO 9+75 & COCKRELL	SIDEWALK ON SIDEROADS	TURN LANE AND BICYCLE LANE ON ARCHER	ADD'L BIKE LANES ON MERCANTILE (4' WIDTH WABASH TO STADIUM)
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 10% STATE 10% CITY	80% FEDERAL 13.3% STATE 6.7% CITY	100% CITY	80% STATE 20% CITY	100% CITY	100% CITY	100% CITY	100% CITY
				0004	0040	0021	0021	0021	0021	0021	0004	0021	0004	0004
* 81702450	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 10	FOOT	4509.0			500.0	3780.0	229.0						
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	9.0			8.0			1.0					
* 82103400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, PHOTO-CELL CONTROL, 400 WATT	EACH	21.0			4.0	16.0	1.0						
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT		2.0			2.0								
* 82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	1.0						1.0					
* 82500330	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 60AMP	EACH	2.0			2.0								
* 83003600	LIGHT POLE, ALUMINUM, 45 FT. M. H. . 15 FT. DAVIT ARM	EACH	9.0			8.0			1.0					
* 83004600	LIGHT POLE, ALUMINUM, 50 FT. M. H. . 15 FT. DAVIT ARM	EACH	2.0			2.0								
* 83600355	LIGHT POLE, METAL, 15" BOLT CIRCLE, 8" X 6' FOUNDATION	EACH	9.0			8.0			1.0					
* 83600357	LIGHT POLE, METAL, 15" BOLT CIRCLE, 8" X 8' FOUNDATION	EACH	2.0			2.0								
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	44.0			40.0			4.0					
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	12.0			12.0								
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	12.0			12.0								

FILE NAME =	USER NAME = sparkge	DESIGNED - AWM	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	FAU ROUTE 8012 (WABASH AVE) SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\sparkge\10373645\0672810-shc-500.dgn	DRAWN - TJD	REVISED -	8012			211W-3, TS-1, RS-71	SANGAMON	679	19	
PLOT SCALE = 100.0000 / in	CHECKED - AWM	REVISED -	CONTRACT NO. 72890							
PLT DATE = Feb-04-2014 04:00:47PM	DATE - 12/04/2013	REVISED -	ILLINOIS FED. AID PROJECT							

* SPECIALTY ITEM