

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				90/10 FED/STATE ROADWAY	90/10 FED/STATE ROADWAY	
				0005 URBAN	0021 URBAN	
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	9	9	
*	81028760	UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.	FOOT	116		116
*	81603045	UNIT DUCT, 600V, 3-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	774		774
*	83600360	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 10" X 6'	EACH	3		3
	84200804	REMOVAL OF POLE FOUNDATION	EACH	3		3
*	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	3		3
	X0322279	OUTLET MARKER	EACH	8		8
	X2010505	CLEARING, SPECIAL	L SUM	1		1
Δ	X7010410	SPEED DISPLAY TRAILER	CAL MO	2	1	1
	X7830072	GROOVING FOR RECESSED PAVEMENT MARKING 6"	FOOT	5501	2730	2771
	Z0016702	DETOUR SIGNING	L SUM	1		1
	Z0022800	FENCE REMOVAL	FOOT	350		350
φ	Z0076600	TRAINEES	HOURL	500	250	250
	Z0034105	MATERIAL TRANSFER DEVICE	TON	1984	1984	
φ	Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOURL	500	250	250
	Z0040530	PIPE UNDERDRAIN REMOVAL	FOOT	2236		2236

*RUTTING *RAMP EXT

* SPECIALTY ITEM

φ 0042

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\dot\sparksg\1d0326237\067	sparksg	DRAWN -	REVISED -		SCALE:	SHEET 1 OF 4 SHEETS	STA.	TO STA.	55	(84-31)-4	SANGAMON	56 7
Default		CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -		CONTRACT NO. 72F90							

Δ REV. 4-15-14