

GUARDRAIL SCHEDULE									
LOCATION		63301210.0	63301215	63301220	63000001	63000007	63100045	78200410	
		REMOVE AND REERECT SPBGR, TYPE A	REMOVE AND REERECT SPBGR, TYPE B	REMOVE AND REERECT SPBGR, TYPE C	SPBGR, TY. A, 6 FT POSTS	SPBGR, TY. B, 6 FT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 2	GUARDRAIL MARKERS, TYPE A	
		FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH	
I-55 MAINLINE									
NORTHBOUND									
STA 166+28	TO	STA 166+66	38.0						
STA 166+66	TO	STA 166+96		31					
STA 166+96	TO	STA 167+19			25				
STA 167+19	TO	STA 167+44		25					
STA 167+44	TO	STA 171+44	400.0						
STA 171+44	TO	STA 171+86		37.5				4	
STA 171+86	TO	STA 172+05			19				
STA 172+05	TO	STA 172+27		22					
STA 172+27	TO	STA 172+47			19				
STA 172+47	TO	STA 172+75		28					
STA 172+75	TO	STA 173+13	38.0						
SOUTHBOUND									
STA 153+51	TO	STA 166+09				1262.5	1	9	
STA 166+09	TO	STA 166+34				25			
STA 166+34	TO	STA 166+59			25				
STA 166+59	TO	STA 166+90		31					
STA 166+90	TO	STA 169+34	238.0						
TOTAL			714.0	174.5	88	1262.5	25	1	13

63200310 GUARDRAIL REMOVAL		
LOCATION		LENGTH
		( FOOT )
I-55 MAINLINE		
NORTHBOUND		
STA 167+13	TO	STA 171+76
		462.5
SOUTHBOUND		
STA 159+62	TO	STA 163+12
		350.0
TOTAL		812.5

DRAINAGE SCHEDULE					
LOCATION		60107600	60108100	60100060	
		PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" ( SPECIAL )	CONC. HEADWALLS FOR PIPE DRAINS	
		FOOT	FOOT	EACH	
I-55 MAINLINE					
NORTHBOUND					
STA 166+35.77			13	1	
STA 166+35.77	TO	STA 170+00.00	364		
STA 170+00.00			14	1	
STA 170+00.00	TO	STA 173+05.55	306		
STA 173+05.55			15	1	
SOUTHBOUND					
STA 153+41.80			17	1	
STA 153+41.80	TO	STA 158+00.00	458		
STA 158+00.00			14	1	
STA 158+00.00	TO	STA 161+50.00	350		
STA 161+50.00			13	1	
STA 161+50.00	TO	STA 165+00.00	350		
STA 165+00.00			19	1	
STA 165+00.00	TO	STA 169+28.10	428		
STA 169+28.10			26	1	
TOTAL			2256	131	8

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -
ct:\pw\work\p\dot\sparksgw\0326237\0672\F90-sht-schedule.dgn		DRAWN -	REVISED -
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -
	PLOT DATE = Oct-17-2013 02:15:12PM	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET 1 OF 3 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(84-3)I-4	SANGAMON	56	8
				CONTRACT NO. 72F90
ILLINOIS FED. AID PROJECT				