

EARTHWORK SCHEDULE					
LOCATION	20200100				20400800
	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	FURNISHED EXCAVATION
	CU. YD.	CU. YD.	CU. YD.	CU. YD.	CU. YD.
I-55 MAINLINE					
NORTHBOUND					
STA 166+36 TO STA 173+06	520	416	232	184	0
SOUTHBOUND					
STA 153+42 TO STA 169+28	1135	908	759	149	141
TOTAL	1655	1324	991	333	141

SEEDING SCHEDULE						
LOCATION	25000200	25000400	25000500	25000600	25000700	
	SEEDING, CL. 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	AGRICULTURAL GROUND LIMESTONE	
	ACRE	POUND	POUND	POUND	TON	
I-55 MAINLINE						
NORTHBOUND						
STA 166+36 TO STA 173+06	0.4	36	36	36	0.8	
SOUTHBOUND						
STA 153+42 TO STA 159+00	0.6	54	54	54	1.2	
STA 161+00 TO STA 169+28	0.2	18	18	18	0.4	
TOTAL	1.2	108	108	108	2.4	

EROSION CONTROL SCHEDULE			
LOCATION	25100115	25100635	
	MULCH, METHOD 2	HEAVY DUTY EROSION CONTROL BLANKET	
	ACRE	SQ. YD.	
I-55 MAINLINE			
NORTHBOUND			
STA 166+36 TO STA 171+00	0.4		
STA 171+00 TO STA 171+76		230	
STA 172+60 TO STA 173+06		40	
SOUTHBOUND			
STA 153+42 TO STA 159+00	0.6		
STA 159+00 TO STA 161+00		694	
STA 161+00 TO STA 169+28	0.2		
TOTAL	1.2	964	

FENCING SCHEDULE	66400405	Z0022800
	CHAIN LINK FENCE 7'	FENCE REMOVAL
LOCATION	LENGTH (FOOT)	LENGTH (FOOT)
I-55 MAINLINE SOUTHBOUND		
STA 159+62 TO STA 163+00	338	338
TOTAL	338	338

X2010505 - CLEARING(SPECIAL)	(LSUM)
I-55 MAINLINE SOUTHBOUND	
STA 159+62 TO STA 163+00	1
TOTAL	1

• CLEARING LIMITS TO FENCE LINE

LOCATION	28000400
	PERIMETER EROSION BARRIER
	FOOT
I-55 MAINLINE	
SOUTHBOUND	
STA 153+00 TO 170+00 LT	1700
NORTH BOUND	
STA 166+00 TO 174+00 RT	800
TOTAL	2500