

SIGN SCHEDULE - ADAMS COUNTY (OUTSIDE MPO)					72000100								72400100	72400200	72400500	72800100	73000100	73100100	73700200	89502375	X0325714	
					SIGN PANEL - TYPE 1								REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	RELOCATE SIGN PANEL ASSEMBLY TYPE A	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE CONCRETE FOUNDATION GROUND MOUNT	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	
LOCATION	CITY OR TOWN	LOCATION DESCRIPTION	ORIENTATION	CROSSWALK(S)	S1-1 (SQ FT)	W11-1 (SQ FT)	W11-2 (SQ FT)	W16-7P(L) (SQ FT)	W16-7P(R) (SQ FT)	W16-9P (SQ FT)	RS PANEL (SQ FT)	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)		
001-01	LIBERTY	IL 104/MAIN ST. & STATE ST.	N-S	SOUTH LEG	36.0			4.4		4.0	4.8	4			64							
001-02	MENDON	IL 61/COLLINS ST. & STATE ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8				48		3					
001-03	MENDON	IL 61/COLLINS ST. & STATE RD.	E-W	WEST LEG			25.0	4.4		4.0	4.8	2			64							
001-04	MENDON	IL 61/COLLINS ST. EAST OF PONDEROSA ST.	E-W	MIDBLOCK	36.0			4.4		4.0	4.8	3			64							
001-05	PAYSON	IL 96/STATE ST. WEST OF WASHINGTON ST.	E-W	MIDBLOCK	36.0			4.4		4.0	4.8		2		64							
001-06	PAYSON	IL 96/STATE ST. & WASHINGTON ST.	E-W	EAST LEG			25.0	4.4		4.0	4.8		2		64		1					
001-07	PAYSON	IL 96/STATE ST. & FULTON ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8	1			64							
001-08	PAYSON	IL 96/STATE ST. & MAIN ST.	E-W	WEST LEG			25.0	4.4		4.0	4.8				64							
001-09	QUINCY	IL 104/BROADWAY ST. & 7TH ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8				64		4					
001-10	QUINCY	IL 104/BROADWAY ST. & 10TH ST.	E-W	E & W LEGS			12.5	4.4		4.0	4.8				32		2					
001-11	QUINCY	IL 104/BROADWAY ST. & 14TH ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8	2			64		4					
001-12	QUINCY	IL 104/BROADWAY ST. & 16TH ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8				64		4					
001-13	QUINCY	IL 104/BROADWAY ST. & 20TH ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8				64		4					
001-14	QUINCY	IL 104/BROADWAY ST. & 22ND ST.	E-W	E & W LEGS			25.0	4.4		4.0	4.8				64		4					
001-15	QUINCY	IL 57/GARDNER EXPRWY. & YORK ST.	N-S	N & S LEGS			25.0	2.2	2.2	4.0	4.8				96		4					
001-16	QUINCY	IL 57/GARDNER EXPRWY. & KENTUCKY ST.	N-S	NORTH LEG			25.0	4.4		4.0	4.8	2			64		2					
001-17	QUINCY	IL 57 & PARK DR. AVE.	N-S	NORTH LEG			25.0	4.4		4.0	4.8				32							
001-18	QUINCY	IL 57/YORK ST. & IL 57/4TH ST.	E-W	WEST LEG			25.0	2.2	2.2	4.0	4.8				64		1					
001-19	QUINCY	US 24/4TH ST. & VERMONT ST.	N-S	N & S LEGS			25.0	2.2	2.2	4.0	4.8				64		4					
001-20	QUINCY	US 24/4TH ST. & LIND ST.	N-S	NORTH LEG			25.0	2.2	2.2	4.0	4.8				64		2					
001-21	QUINCY	US 24/4TH ST. & CHESTNUT ST.	N-S	N & S LEGS			25.0	2.2	2.2	4.0	4.8				64		4					
001-22	QUINCY	IL 96/24TH ST. & HAMPSHIRE ST.	N-S	NORTH LEG			25.0	4.4		4.0	4.8				64		2					
001-23	QUINCY	IL 96/24TH ST. & JERSEY ST.	N-S	NORTH LEG			25.0	4.4		4.0	4.8				64		2					
TOTALS					108.0	0.0	487.5	90.2	11.0	92.0	110.4	14	4	0	1,424	0	47	0	0	0	0	
					899.1																	

SIGN SCHEDULE - BROWN COUNTY (OUTSIDE MPO)					72000100								72400100	72400200	72400500	72800100	73000100	73100100	73700200	89502375	X0325714	
					SIGN PANEL - TYPE 1								REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	RELOCATE SIGN PANEL ASSEMBLY TYPE A	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE CONCRETE FOUNDATION GROUND MOUNT	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	
LOCATION	CITY OR TOWN	LOCATION DESCRIPTION	ORIENTATION	CROSSWALK(S)	S1-1 (SQ FT)	W11-1 (SQ FT)	W11-2 (SQ FT)	W16-7P(L) (SQ FT)	W16-7P(R) (SQ FT)	W16-9P (SQ FT)	RS PANEL (SQ FT)	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)		
005-01	MT. STERLING	US 24/MAIN ST. & NORTH ST.	E-W	EAST LEG																		
005-02	MT. STERLING	US 24/IL 99/MAIN ST. EAST OF W. CROSS ST.	E-W	MIDBLOCK			25.0	4.4		4.0	4.8	2			32		2					
005-03	MT. STERLING	IL 99/WASHINGTON ST. & IL 99/CAMDEN ST.	E-W TO NORTH	NORTH LEG	36.0			4.4		4.0	4.8				64							
005-04	VERSAILLES	IL 99/MAIN ST. & 2ND ST.	N-S	SOUTH LEG			25.0	4.4		4.0	4.8	2			64		2					
TOTALS					36.0	0.0	50.0	13.2	0.0	12.0	14.4	4	0	0	160	0	4	0	0	0	0	
					125.6																	

SIGN SCHEDULE - CASS COUNTY (OUTSIDE MPO)					72000100								72400100	72400200	72400500	72800100	73000100	73100100	73700200	89502375	X0325714	
					SIGN PANEL - TYPE 1								REMOVE SIGN PANEL ASSEMBLY TYPE A	REMOVE SIGN PANEL ASSEMBLY TYPE B	RELOCATE SIGN PANEL ASSEMBLY TYPE A	TELESCOPING STEEL SIGN SUPPORT	WOOD SIGN SUPPORT	BASE FOR TELESCOPING STEEL SIGN SUPPORT	REMOVE CONCRETE FOUNDATION GROUND MOUNT	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION	
LOCATION	CITY OR TOWN	LOCATION DESCRIPTION	ORIENTATION	CROSSWALK(S)	S1-1 (SQ FT)	W11-1 (SQ FT)	W11-2 (SQ FT)	W16-7P(L) (SQ FT)	W16-7P(R) (SQ FT)	W16-9P (SQ FT)	RS PANEL (SQ FT)	(EACH)	(EACH)	(EACH)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)		
009-01	VIRGINIA	IL 78/MAIN ST. & SPRINGFIELD ST.	N-S	NORTH LEG			18.8	4.4		2.0	3.6	1			48		3					
009-02	VIRGINIA	IL 78/MAIN ST. SOUTH OF SPRINGFIELD ST.	N-S	MIDBLOCK			12.5	4.4			2.4				32		2					
009-03	VIRGINIA	IL 78/MAIN ST. & BEARDSTOWN ST.	N-S	SOUTH LEG			18.8	4.4		2.0	3.6	1			48		3					
009-04	VIRGINIA	IL 78/MAIN ST. & ILLINI ST.	N-S	SOUTH LEG																		
TOTALS					0.0	0.0	50.0	13.2	0.0	4.0	9.6	2	0	0	128	0	8	0	0	0	0	
					76.8																	

- SIGNING ONLY AT THIS LOCATION. CONTRACT #72G03 WILL ADDRESS STRIPING AT THIS LOCATION.
- LOCATION OMITTED DUE TO ONGOING SAFE ROUTES TO SCHOOL (SRTS) PROJECT. SRTS WILL ADDRESS THIS LOCATION.
- STRIPING ONLY AT THIS LOCATION

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ci:\pw\work\p\dot\sparksgw\10360886\0672076-sh-t-schedule.dgn	2076-sh-t-schedule.dgn	DRAWN -	REVISED -						VAR			58	5
Default	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		SCALE: SHEET 1 OF 10 SHEETS STA. TO STA.				ILLINOIS FED. AID PROJECT				
	PLOT DATE = Feb-04-2014 03:48:28PM	DATE -	REVISED -						CONTRACT NO. 72G76				