

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FEDERAL 10% STATE CONSTRUCTION CODE			
				VARIOUS COUNTIES	SANGAMON	VARIOUS COUNTIES	SANGAMON
				PAVEMENT MARKING	PAVEMENT MARKING	TRAFFIC SIGN	TRAFFIC SIGN
				0021 RURAL	0021 URBAN	0021 RURAL	0021 URBAN
67100100	MOBILIZATION	L SUM	1	0.4	0.1	0.4	0.1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.4	0.1	0.4	0.1
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	0.4	0.1	0.4	0.1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.4	0.1	0.4	0.1
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	0.4	0.1	0.4	0.1
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	0.4	0.1	0.4	0.1
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.4	0.1	0.4	0.1
72000100	SIGN PANEL - TYPE 1	SQ FT	4252.5			3940.8	311.7
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	89			88	1
72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	72			65	7
72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	7			7	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	6048			5728	320
73000100	WOOD SIGN SUPPORT	FOOT	128			128	
73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	143			137	6

FILE NAME : c:\pwork\pwork\spksgn\036006\067078-41-500.dgn	USER NAME : spksgn	DESIGNED -	REVISOR -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. +	SECTION	COUNTY	TOTAL	SHEET
PLOT SCALE : 100.0000 / in	DATE	DRAWN -	REVISOR -						VAR			SS	3
PLOT DATE : Feb-04-2014 03:39:12PM		CHECKED -	REVISOR -		SCALE: SHEET 1 OF 2 SHEETS STA. TO STA.				CONTRACT NO. 72076				
Default		DATE	REVISOR -						ILLINOIS FED. AID PROJECT				