

SIGNING SCHEDULE – OUTSIDE MPO (CONT.)

LOCATION	MUTCD	DIMENSIONS	AREA OF EACH SIGN (SQ FT)	NO. OF SIGNS	CHEVRON SIGNING SPACING (FOOT)	PROPOSED POST LENGTH (FOOT)	72000100	72000200	72400100	72800100	73000100	X0325714	BLINDER FOR SIGN (EACH)
							SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE A (EACH)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	WOOD SIGN SUPPORT (FOOT)	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION (EACH)	
SANGAMON COUNTY													
084-06	W1-8	18" X 24"	3.0	32	160	12	96.0				192		
	RS PANEL(A)	2" X 60"	0.8	32			25.6						
084-07	W2-1	30" X 30"	6.3	2		14	12.5				28		
	W16-80P(EB)	48" X 15"	5.0	1			5.0						
	W16-80P(WB)	48" X 15"	5.0	1			5.0						
084-08	R1-1	30" X 30"	6.3	1		13	6.3				13		
	W1-7	48" X 24"	8.0	1		12	8.0				24		
	W3-1	30" X 30"	6.3	1		14	6.3				14		
SCHUYLER COUNTY													
085-01	RS PANEL(A)	2" X 60"	0.8	40			32.0						
085-02	W1-8	18" X 24"	3.0	10	120	12	30.0				60		
OUTSIDE MPO SUB TOTALS							226.6	0.0	0	331	0	0	0
OUTSIDE MPO TOTALS							1,289.0	32.0	6	2,458	30	4	3

SIGNING SCHEDULE – INSIDE MPO

LOCATION	MUTCD	DIMENSIONS	AREA OF EACH SIGN (SQ FT)	NO. OF SIGNS	CHEVRON SIGNING SPACING (FOOT)	PROPOSED POST LENGTH (FOOT)	72000100	72000200	72400100	72800100	73000100	X0325714	BLINDER FOR SIGN (EACH)
							SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE A (EACH)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	WOOD SIGN SUPPORT (FOOT)	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION (EACH)	
SANGAMON COUNTY													
084-01	RS PANEL(B)	2" X 84"	1.2	34			40.8						
084-02	RS PANEL(B)	2" X 84"	1.2	42			50.4						
084-04	W3-3	30" X 30"	6.3	1		14	6.3			14			
084-09	W1-10(L)	36" X 36"	9.0	2		15	18.0			30			
	W16-8P	36" X 8"	2.0	2			4.0						
084-10	W1-5(L)	30" X 30"	6.3	1		14	6.3			14			
	W1-5(R)	30" X 30"	6.3	1		14	6.3			14			
INSIDE MPO TOTALS							132.0	0.0	0	72	0	0	0

SIGNING SCHEDULE – PROJECT TOTALS

LOCATION	72000100	72000200	72400100	72800100	73000100	X0325714	BLINDER FOR SIGN (EACH)
	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE A (EACH)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	WOOD SIGN SUPPORT (FOOT)	FLASHING BEACON, POST MOUNTED, SOLAR POWERED INSTALLATION (EACH)	
OUTSIDE MPO TOTALS	1,289.0	32.0	6	2,458	30	4	3
INSIDE MPO TOTALS	132.0	0.0	0	72	0	0	0
PROJECT TOTALS	1,420.9	32.0	6	2,530	30	4	3