

SUMMARY OF QUANTITIES				90% FED 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 026-0106 & 0107
20101000	TEMPORARY FENCE	FOOT	2950	2950	
20200100	EARTH EXCAVATION	CU YD	9280	9280	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	19400	19400	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1020	1020	
25000210	SEEDING, CLASS 2A	ACRE	8.5	8.5	
25000350	SEEDING, CLASS 7	ACRE	8.5	8.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	765	765	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	765	765	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	765	765	
25000700	AGRICULTURAL GROUND LIMESTONE	TON	17	17	
25100115	MULCH, METHOD 2	ACRE	16.5	16.5	
25100630	EROSION CONTROL BLANKET	SQ YD	2906	2906	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1700	1700	
28000305	TEMPORARY DITCH CHECKS	FOOT	420	420	

PRINT GROUP - LARGE SCALE
 FILE NAME - 177175.dwg
 PLOT DATE - 1/29/2014 1:36:18 PM



USER NAME * has
 ESCA PROJECT NO. 1000.03
 PLOT SCALE * 2:1667 / 1 IN.
 PLOT DATE * 1/29/2014 1:36:18 PM

DESIGNED - ELH
 DRAWN - HAS
 CHECKED - RDP
 DATE - 01/14

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE SHEET NO. 1 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	126-3B-1, 3B-1(3)BR	FAYETTE	277	4
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74175	