

SUMMARY OF QUANTITIES				90% FED 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 026-0106 & 0107
28000400	PERIMETER EROSION BARRIER	FOOT	1310	1310	
28000500	INLET AND PIPE PROTECTION	EACH	4	4	
28100107	STONE RIPRAP, CLASS A4	SQ YD	3600		3600
28200200	FILTER FABRIC	SQ YD	3600		3600
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	11980	11980	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SQ YD	2114	2114	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2188	2188	
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	40	40	
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1008	1008	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	208	208	
42000515	PORTLAND CEMENT CONCRETE PAVEMENT 10 3/4"	SQ YD	5375	5375	
42001200	PAVEMENT FABRIC	SQ YD	5375	5375	
42001300	PROTECTIVE COAT	SQ YD	5375	5375	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	288	288	

PRINT CHECKED - JUNE 18, 2014
 USER: JHONAS
 FILE NAME: 137175.dwg



USER NAME * jhon
 ESCA PROJECT NO. 126-38-05
 PLOT SCALE * 2.1667" / IN.
 PLOT DATE * 1/29/2014 1:38:25 PM

DESIGNED - ELH
 DRAWN - HAS
 CHECKED - RDP
 DATE - 01/14

REVISIONS:
 REVISIONS -
 REVISIONS -
 REVISIONS -
 REVISIONS -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
 SCALE SHEET NO. 2 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	126-38-1, 3B-1(3)BR	FAYETTE	277	5
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74175	