

SUMMARY OF QUANTITIES				90% FED 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S.N. 026-0106 & 0107
50300100	FLOOR DRAINS	EACH	87		87
50300225	CONCRETE STRUCTURES	CU YD	3186.2		3186.2
50300255	CONCRETE SUPERSTRUCTURE	CU YD	3516.1		3516.1
50300260	BRIDGE DECK GROOVING	SQ YD	10182		10182
50300265	SEAL COAT CONCRETE	CU YD	659.1		659.1
50300280	CONCRETE ENCASEMENT	CU YD	32.8		32.8
50300300	PROTECTIVE COAT	SQ YD	12831		12831
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	37692		37692
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1391470		1391470
50800515	BAR SPLICERS	EACH	168		168
50800530	MECHANICAL SPLICERS	EACH	1252		1252
51201800	FURNISHING STEEL PILES HP14X73	FOOT	5625		5625
51201900	FURNISHING STEEL PILES HP14X89	FOOT	25768		25768

PRINT CHECKED - LAY LAYOUT  
 REVISED - 1/29/2014  
 FILE NAME - 110104.dwg  
 PLOT DATE - 1/29/2014



USER NAME - hax	DESIGNED - ELH	REVISED -
ESCA PROJECT NO. 1005.05	DRAWN - HAS	REVISED -
PLOT SCALE - 0.1667 "/> IN.	CHECKED - RDP	REVISED -
PLOT DATE - 1/29/2014 11:48:55 PM	DATE - 01/14	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SUMMARY OF QUANTITIES</b>	
SCALE	SHEET NO. 4 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-38-1, 38-113)BR	FAYETTE	277	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74175	