

SUMMARY OF QUANTITIES				90% FED 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 026-0106 & 0107
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	2	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	32	32	
67100100	MOBILIZATION	L SUM	1	1	
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	6	6	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	35	35	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	2602	2602	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	27860	27860	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	8510	8510	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	8962.5	8962.5	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4187.5	4187.5	
70500665	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2	
78003130	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	FOOT	830	830	
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	21100	21100	

ESCA
 11/29/2014 1:32:16 PM
 144



USER NAME * hox	DESIGNED - ELH	REVISED -
ESCA PROJECT NO. 1000.05	DRAWN - HAS	REVISED -
PLOT SCALE * 0.1667 1/8 IN.	CHECKED - RDP	REVISED -
PLOT DATE * 1/29/2014 1:32:16 PM	DATE - 01/14	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE	SHEET NO. 7 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-3B-1, 3B-1(3))BR	FAYETTE	277	10
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 74175	