

SUMMARY OF QUANTITIES				90% FED 10% STATE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004	0011
				RURAL	S. N. 026-0106 & 0107
78009008	MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	FOOT	970	970	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	22	22	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	56	56	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	21	21	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	4325	4325	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	22	22	
54210024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	300	300	
542A0229	PIPE CULVERTS, CLASS A, TYPE 1 24"	FOOT	10	10	
542D0220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	49	49	
542D0229	PIPE CULVERTS, CLASS D, TYPE 1 24"	FOOT	864	864	
X0301993	REMOVE AND REINSTALL CONCRETE HEADWALL FOR PIPE DRAIN	EACH	1	1	
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1603	1603	
X5210120	HIGH LOAD MULTI-ROTATIONAL BEARINGS, GUIDED EXPANSION, 250K	EACH	6		6

14

ESCA CONSULTANTS, INC. 1101 W. MONROE ST. SUITE 200 CHICAGO, IL 60606
 TEL: 312.467.1100 FAX: 312.467.1101
 WWW.ESCA-CONSULTANTS.COM



USER NAME * Has	DESIGNED - ELH	REVISED -
ESCA PROJECT NO. 1020.05	DRAWN - HAS	REVISED -
PLOT SCALE = 0.1667" = 1' IN.	CHECKED - RDP	REVISED -
PLOT DATE = 1/29/2014 1:32:03 PM	DATE - 01/14	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES	
SCALE	SHEET NO. 8 OF 10 SHEETS
STA.	TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	(26-3B-1, 3B-1(3))BR	FAYETTE	277	11
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 74175	