

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0004	
X0327727	PLANTER REMOVAL	L SUM	1	1	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	399	399	
20400800	FURNISHED EXCAVATION	CU YD	39	39	
20800150	TRENCH BACKFILL	CU YD	4	4	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	25	25	
30200650	PROCESSING MODIFIED SOIL 12"	SO YD	14115	14115	
30300011	AGGREGATE SUBGRADE IMPROVEMENT	TON	76	76	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1072	1072	
40600300	AGGREGATE (PRIME COAT)	TON	21	21	
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	592	592	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	176	176	
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	889	889	
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	SO YD	14115	14115	

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0004	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SO FT	2868	2868	
42400800	DETECTABLE WARNINGS	SO FT	78	78	
44000100	PAVEMENT REMOVAL	SO YD	14115	14115	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	153	153	
44000600	SIDEWALK REMOVAL	SO FT	2332	2332	
44004250	PAVED SHOULDER REMOVAL	SO YD	53	53	
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	53	53	
50105220	PIPE CULVERT REMOVAL	FOOT	35	35	
54215547	METAL END SECTIONS 12"	EACH	4	4	
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	35	35	
60609300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.12 (ABUTTING EXISTING PAVEMENT)	FOOT	164	164	
67100100	MOBILIZATION	L SUM	1	1	
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD 701451	L SUM	1	1	

FILE NAME =	USER NAME = staffennk	DESIGNED -	REVISED -
c:\pwwork\pwwork\staffennk\dms67460\0774284-ans-ssn.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET 1	OF 2 SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	15B-66)RA-1-1	MACON	56	3
CONTRACT NO. 74284				
ILLINOIS FED. AID PROJECT				