

EARTHWORK AND SEEDING SCHEDULE

NUMBER	LOCATION	COUNTY	SIDE OF ROAD	EARTH EXCAVATION				SEEDING			
				CU	YD	CU	YD	LB	ACRE	CU	YD
4	FAIRWAY VIEW CIRCLE UNDER I-57 NEAR MATTOON	COLES	WEST	0	68	10.5	0.105				
6	IL 48 UNDER I-72 IN DECATUR	MACON	WEST	0	4	1.3	0.013				
7	IL 48 UNDER I-72 NORTHEAST OF DECATUR	MACON	NORTH	0	4	1.3	0.013				
8	IL 121 UNDER I-72 IN DECATUR	MACON	NORTH	0	4	1.3	0.013				
9	IL 48 UNDER US 51 IN DECATUR	MACON	NORTH	0	4	1.3	0.013				
10	OLD US 51 OVER US 51 IN DECATUR	MACON	EAST	0	4	1.3	0.013				
12	US 45 UNDER I-64	WAYNE	CENTER	89							
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	WEST	0	8	2.6	0.026				
TOTAL =				89	96	20	0.20				

44000500 COMBINATION CURB AND GUTTER REMOVAL

NUMBER	LOCATION	COUNTY	FOOT
12	US 45 UNDER I-64	WAYNE	831.0
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	867.0
TOTAL =			1698.0

44003100 MEDIAN REMOVAL

NUMBER	LOCATION	COUNTY	SQ FT
12	US 45 UNDER I-64	WAYNE	2193.0
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	5784.0
TOTAL =			7977.0

48101200 AGGREGATE SHOULDERS TYPE B

NUMBER	LOCATION	COUNTY	SIDE OF ROAD	TONS
1	TOWNSHIP ROAD 950E UNDER I-70	CUMBERLAND	WEST	18.8
1	TOWNSHIP ROAD 950E UNDER I-71	CUMBERLAND	EAST	15.0
2	OLD IL 140 UNDER I-70	FAYETTE	NORTH	5.7
3	BROAD ST. UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	WEST	22.8
4	FAIRWAY VIEW CIRCLE UNDER I-57 NEAR MATTOON	COLES	WEST	29.9
5	DEWITT AVE (IL 316) UNDER I-57 IN MATTOON	COLES	NORTH	23.7
6	IL 48 UNDER I-72 IN DECATUR	MACON	WEST	9.5
7	IL 48 UNDER I-72 NORTHEAST OF DECATUR	MACON	NORTH	49.0
8	IL 121 UNDER I-72 IN DECATUR	MACON	NORTH	8.5
9	IL 48 UNDER US 51 IN DECATUR	MACON	NORTH	7.9
10	OLD US 51 OVER US 51 IN DECATUR	MACON	EAST	8.2
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	EAST	3.2
13	751st ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	WEST	3.5
TOTAL =				205.9
NOTE: AGGREGATE SHOULDERS SHALL BE USED ALONG GUARDRAIL AS DETERMINED BY THE ENGINEER.				USE = 206.0

60608250 COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06

NUMBER	LOCATION	COUNTY	FOOT
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	867.0
TOTAL =			867.0

60608300 COMBINATION CONCRETE CURB & GUTTER, TYPE M-2.12

NUMBER	LOCATION	COUNTY	FOOT
12	US 45 UNDER I-64	WAYNE	831.0
TOTAL =			831.0

60618300 CONCRETE MEDIAN SURFACE, 4"

NUMBER	LOCATION	COUNTY	SQ FT
12	US 45 UNDER I-64	WAYNE	5386.0
13	750th ST UNDER I-57 NEAR EDGEWOOD	EFFINGHAM	5784.0
TOTAL =			11170.0