

DELINEATORS							
LOCATION				DELINEATOR REMOVAL EACH	DELINEATORS		
STA.	TO	STA.	LT/RT		(AMBER) EACH	(WHITE) EACH	DOUBLE (WHITE) EACH
I-70 WESTBOUND							
2778+74.10	TO	3038+61.99	LT	65		65	
I-70 EASTBOUND							
2778+74.10	TO	3038+61.99	RT	65		65	
MULBERRY GROVE RAMPS							
RAMP I - WB EXIT							
00+00.00	TO	06+62.40	RT	7			7
06+62.40	TO	14+75.00	RT	10		10	
06+62.40	TO	14+75.00	LT	10	10		
RAMP II - EB ENTRANCE							
01+00.00	TO	12+80.00	RT	17		17	
01+00.00	TO	12+80.00	LT	17	17		
12+80.00	TO	23+49.96	RT	12			12
RAMP III - EB EXIT							
00+00.00	TO	06+62.40	RT	7			7
06+62.40	TO	17+22.00	RT	15		15	
06+62.40	TO	17+22.00	LT	15	15		
RAMP IV - WB ENTRANCE							
01+00.00	TO	08+66.00	RT	12		12	
01+00.00	TO	08+66.00	LT	12	12		
08+66.00	TO	16+09.26	RT	8			8
SUBTOTAL				272	54	184	34
TOTAL				272		272	

RAISED FLECTIVE PAVEMENT MARKERS			
LOCATION			
RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
RAISED REFLECTIVE PAVEMENT MARKER			
RAISED REFLECTIVE PAVEMENT MARKER			
RAISED REFLECTIVE PAVEMENT MARKER			
EACH			
(CRYSTAL) EACH			
(AMBER) EACH			
I-70 WESTBOUND			
2778+74.10	TO	3038+61.99	650
I-70 EASTBOUND			
2778+74.10	TO	3038+61.99	650
MULBERRY GROVE RAMPS			
RAMP I - WB EXIT			
00+00.00	TO	07+10.85	36
02+81.81	TO	07+10.85	21
07+10.85	TO	10+93.53	10
RAMP III - EB EXIT			
00+00.00	TO	07+09.48	35
02+88.75	TO	07+09.48	21
07+09.48	TO	11+53.75	11
SUBTOTAL			1342
TOTAL			1342
			1413
			1442

PAVEMENT MARKING SCHEDULE											
LOCATION				PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6", SOLID		PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 6" SKIP DASH		PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8" SOLID		PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8" SKIP DASH	
STA	TO	STA	LT/CL/RT	(WHITE) FOOT	(YELLOW) FOOT	(WHITE) FOOT	(WHITE) FOOT	(WHITE) FOOT	(WHITE) FOOT	(WHITE) FOOT	
I-70 WESTBOUND											
2778+74.10	TO	3038+61.99	LT/CL/RT	25460	25988	6497	528				
I-70 EASTBOUND											
2778+74.10	TO	3038+61.99	LT/CL/RT	25454	25988	6497	534				
MULBERRY GROVE RAMPS											
RAMP I - WB EXIT											
00+00.00	TO	15+67.00	RT	1567							
2+88.75	TO	7+09.48	LT				421				
7+09.48	TO	15+67.00	LT		858						
RAMP II - EB ENTRANCE											
00+12.34	TO	23+49.96	RT	2338							
00+12.34	TO	12+32.89	LT		1221						
12+32.89	TO	13+37.75	LT				105				
13+37.75	TO	15+85.18	LT						62		
RAMP III - EB EXIT											
00+00.00	TO	18+19.86	RT	1820							
2+81.81	TO	7+10.85	LT				429				
7+10.85	TO	18+19.86	LT		1109						
RAMP IV - WB ENTRANCE											
00+14.00	TO	20+83.57	RT	2070							
00+14.00	TO	8+14.00	LT		800						
8+14.00	TO	9+21.40	LT				107				
9+21.40	TO	13+42.51	LT						105		
SUB-TOTAL				58708	55963	12994	2124		167		
TOTAL					127665		2291				

SHORT TERM PAVEMENT MARKING SCHEDULE					
LOCATION			SHORT TERM PAVEMENT MARKING - LINE 4" SKIP DASH	SHORT TERM PAVEMENT MARKING - LINE 4" EDGE LINE	WORK ZONE PAVEMENT MARKING REMOVAL
STA	TO	STA	FOOT	FOOT	SQ FT
I-70 WESTBOUND					
2778+74.10	TO	3038+61.99	2363	2079	3711
I-70 EASTBOUND					
2778+74.10	TO	3038+61.99	2363	2079	3711
MULBERRY GROVE RAMPS					
RAMP I - WB EXIT					
06+62.40	TO	15+87.65		74	49
RAMP II - EB ENTRANCE					
00+00.00	TO	14+00.00		112	74
RAMP III - EB EXIT					
06+62.40	TO	18+35.19		94	62
RAMP IV - WB ENTRANCE					
00+00.00	TO	09+32.02		75	25
SUBTOTAL			4725	4512	7631
TOTAL				9238	7631