

PIPE UNDERDRAIN AND PIPE DRAIN SCHEDULE

ROADWAY	LOCATION		SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDERDRAIN REMOVAL	PIPE UNDERDRAINS, 6"	PIPE UNDERDRAINS, 6" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS & SYMBOLS	OUTLET & HEADWALL 601101	REMARKS	
FAI 70 EB RT	2782+04	2787+40	536	557	536	21	1	2	2787+40	2782+04 OUTLET INTO CULVERT HEADWALL PLUG AT SUMMIT AT PLUG AT	
	2787+44	2792+00	456	477	456	21	1	2	2792+00		
	2792+04	2797+00	496	517	496	21	1	2	2797+00		
	2797+04	2802+00	496	517	496	21	1	2	2802+00		
	2802+04	2807+00	496	517	496	21	1	2	2807+00		
	2807+04	2812+00	496	517	496	21	1	2	2812+00		
	2812+04	2817+00	496	517	496	21	1	2	2817+00		
	2817+04	2822+00	496	517	496	21	1	2	2822+00		
	2822+04	2826+50	446	467	446	21	1	2	2826+50		
	2826+54	2827+50	96	117	96	21	1	2	TEE AT 2830+96		
	2827+50	2830+96	346	346	346				2827+50		
	2831+00	2835+96	496	517	496	21	1	2	2831+00		
	2836+00	2840+96	496	517	496	21	1	2	2836+00		
	2841+00	2845+96	496	517	496	21	1	2	2841+00		
	2846+00	2850+96	496	517	496	21	1	2	2846+00		
	2851+00	2854+96	396	417	396	21	1	2	2851+00		
	2855+00	2858+00	300	321	300	21	1	2	2855+00		
	2858+00	2863+00	500	521	500	21	1	2	2863+00		
	2863+04	2868+00	496	517	496	21	1	2	2868+00		
	2868+04	2872+00	396	417	396	21	1	2	2872+00		
	2872+04	2873+50	146	167	146	21	1	2	TEE AT 2873+50		
	2873+50	2876+96	346	346	346				2873+50		
	2877+00	2881+96	496	517	496	21	1	2	2877+00		
	2882+00	2886+96	496	517	496	21	1	2	2882+00		
SUBTOTAL THIS SCHEDULE			10412	10874	10412	462	22	44			