

PIPE UNDERDRAIN AND PIPE DRAIN SCHEDULE

ROADWAY	LOCATION		SHOULDER REMOVAL AND REPLACEMENT 5"	PIPE UNDERDRAIN REMOVAL	PIPE UNDER-DRAINS, 6"	PIPE UNDER-DRAINS, 6" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS & SYMBOLS	OUTLET & HEADWALL 601101	REMARKS	
	OUTSIDE	OUTSIDE	OUTSIDE	OUTSIDE	OUTSIDE	OUTSIDE	OUTSIDE	OUTSIDE			
FAI 70 EB RT	2887+00	2889+00	200	221	200	21	1	2	2887+00	SUMMIT AT	2889+00
	2889+00	2894+00	500	521	500	21	1	2	2894+00		
	2894+04	2899+00	496	517	496	21	1	2	RAMP III STA. 3+87 RT 2999+00	PLUG AT	2894+04
	2900+45	2906+00	555	576	555	21	1	2	2906+00		2900+45
	2906+04	2911+00	496	517	496	21	1	2	2911+00		2906+04
	2911+04	2916+00	496	513	496	17	1	2	2916+00		2911+04
	2916+04	2921+00	496	513	496	17	1	2	TEE AT 2921+00		2916+04
	2921+00	2923+00	200	200	200				2921+00		SUMMIT AT
	2923+00	2925+03	203	246	203	43	1	2	2925+03	PLUG AT	2925+07
	2925+07	2930+00	493	514	493	21	1	2	2930+00		2930+04
	2930+04	2935+00	496	513	496	17	1	2	2935+00		2935+04
	2935+04	2940+00	496	517	496	21	1	2	2940+00		2940+04 OUTLET INTO CULVERT HEADWALL
	2940+04	2943+80	376	389	376	13	1	2	2943+80		2943+84
	2943+84	2948+69	485	502	485	17	1	2	2948+69		
	RAMP II RT	11+75	14+00	225	225	225		1	2	14+00	OUTLET INTO STORM SEWER. TYPE 1, 4' (PUSHED) STA. 7+52
	RAMP II LT	11+75	14+00	225	225	225		1	2	14+00	
RAMP III RT	03+91	07+52	361	399	361	38	1	2	07+52	OUTLET INTO STORM SEWER. TYPE 1, 4' (PUSHED) Sta. 7+52	
RAMP III LT	03+34	07+52	418	418	418		1	2	07+52		
FAI 70 EB LT	2782+04	2787+57	553	578	553	25	1	2	2787+54	PLUG AT	2782+04
	2787+60	2792+00	440	461	440	21	1	2	2792+00		2787+60
	2792+04	2797+00	496	517	496	21	1	2	2797+00		2792+04
	2797+04	2807+00	496	517	496	21	1	2	2802+00		2797+04
SUBTOTAL THIS SCHEDULE			9202	9599	9202	397	21	42			