

90% FEDERAL 10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BRIDGE	BRIDGE	BRIDGE	TRAFFIC SIGNS
				0005	0014	0014	0014	0021
				RURAL	003-0036	003-0045	003-0046	NONE
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	452	452				
20100500	TREE REMOVAL, ACRES	ACRE	9.5	9.5				
20200100	EARTH EXCAVATION	CU YD	2142	2142				
20400800	FURNISHED EXCAVATION	CU YD	2733	2733				
21400100	GRADING AND SHAPING DITCHES	FOOT	1885	1885				
25000210	SEEDING, CLASS 2A	ACRE	5	5				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	405	405				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	405	405				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	405	405				
25100115	MULCH, METHOD 2	ACRE	5	5				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	450	450				
28000305	TEMPORARY DITCH CHECKS	FOOT	19	19				
28000500	INLET AND PIPE PROTECTION	EACH	2	2				
28100801	STONE DUMPED RIPRAP, CLASS A1	TON	171.7	171.7				

FILE NAME = c:\pwwork\psidot\wedmore\j\08149884\0816021-ah1-500.dgn
 USER NAME = wedmore\j
 PLOT SCALE = 1/8" = 100.0000' / 1" / in.
 PLOT DATE = 3/18/2014

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 1 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TO	3-5RS-3	BOND	59	3
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76 D21	