

90% FEDERAL 10% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE				
				ROADWAY	BRIDGE	BRIDGE	BRIDGE	TRAFFIC SIGNS
				0005 RURAL	0014 003-0036	0014 003-0045	0014 003-0046	0021 NONE
70100205	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	EACH	2	2				
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	6	6				
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4	4				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1		0.4	0.3	0.3	
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1	1				
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	60	60				
70300100	SHORT TERM PAVEMENT MARKING	FOOT	9238	9238				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	117757	117757				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	949	949				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	7631	7631				
70400100	TEMPORARY CONCRETE BARRIER	FOOT	3138	3138				
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	3138	3138				
70600340	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 2	EACH	6	6				
* 72000300	SIGN PANEL - TYPE 3	SQ FT	947.5					947.5

* SPECIALTY ITEM

FILE NAME =	USER NAME = wedmore.jb	DESIGNED -	REVISED -
c:\pwwork\pwwork\wedmore.jb\20140824\08	6021-shi-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -
	PLOT DATE = 3/18/2014	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. 5 OF 7 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
70	3-5RS-3	BOND	59	7
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76 D21	