

PAVEMENT WIDENING SCHEDULE						
LOCATION			BITUMINOUS MATERIALS (PRIME COAT) 3 LIFTS (TON)	AGGREGATE (PRIME COAT) 3 LIFTS (TON)	HMA PAVEMENT (FULL-DEPTH), 11-1/4" (SQ YD)	SUBBASE GRANULAR MATERIAL, TYPE B, 12" (SQ YD)
STA	TO	STA	(TON)	(TON)	(SQ YD)	(SQ YD)
IL 4 - RIGHT						
769+45	TO	773+85	1.3	2	269	522
773+85	TO	775+31	0.8	1	178	262
775+31	TO	778+13	1.8	3	376	538
778+13	TO	782+96.5	1.5	2	322	600
TOTAL:			5	9	1146	1922

HMA SHOULDER SCHEDULE							
LOCATION			BITUMINOUS MATERIALS (PRIME COAT) 2 LIFTS (TON)	AGGREGATE (PRIME COAT) 2 LIFTS (TON)	HMA SHOULDERS, 8" (SQ YD)	PAVED SHOULDER REMOVAL (SQ YD)	SUBBASE GRANULAR MATERIAL, TYPE C (CU YD)
STA	TO	STA	(TON)	(TON)	(SQ YD)	(SQ YD)	(CU YD)
IL 4 - RIGHT							
768+65	TO	775+31	0.7	1	222		35
775+31	TO	781+14	0.8	1	259	259	30
781+14	TO	782+96.5	0.3	0	81	81	9
TOTAL:			2	3	562	340	74

RESURFACING SCHEDULE						
LOCATION			BITUMINOUS MATERIALS (PRIME COAT) 3 LIFTS (TON)	AGGREGATE (PRIME COAT) 3 LIFTS (TON)	POLY HMA SURFACE COURSE, MIX D, N90 - 2-1/2" (TON)	HMA SURFACE REMOVAL, 2-1/2" (SQYD)
STA	TO	STA	(TON)	(TON)	(TON)	(SQYD)
IL 4 - RIGHT						
768+65	TO	775+31	4.9	8	145	1036
775+31	TO	778+64.03	2.3	4	67	481
778+64.03	TO	782+96.5	2.9	5	87	625
TOTAL:			10	16	300	2142

RIGHT OF WAY MARKER SCHEDULE			
LOCATION	RT/LT	OFFSET (FEET)	FURNISHING AND ERECTING ROW MARKERS (EACH)
776+50	RT	60	1
776+00	RT	65	1
774+50	RT	65	1
773+74.98	RT	75	1
769+03.28	RT	75	1
TOTAL:			5

PIPE UNDERDRAINS 4" (SPECIAL)				
LOCATION	PIPE UNDERDRAIN 4" (SPECIAL) (FOOT)	CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	PIPE UNDERDRAIN REMOVAL (SPECIAL) (FOOT)	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)
IL 4 - RIGHT				
769+00	10	1		
772+00	15	1		
775+50	18	1	19	1
779+00	12	1		
782+96.5	12	1		
TOTAL:		67	5	19

AGGREGATE SHOULDER SCHEDULE			
LOCATION			AGGREGATE SHOULDERS, TYPE A - 6" (TON)
STA	TO	STA	(TON)
IL 4 - RIGHT			
768+65	TO	769+12	3.7
769+58	TO	776+82	56.3
777+46	TO	780+03	20.0
780+92	TO	783+46.5	19.8
TOTAL:			100

ENTRANCE SCHEDULE				
LOCATION	area (SQ YD)	AGGREGATE SURFACE COURSE, TYPE A - 6" (SQ YD)	PIPE CULVERTS, CLASS D, TYPE 1 15" (FEET)	PIPE CULVERT REMOVAL (FEET)
IL 4 - RIGHT				
769+36	143	142.6	50.0	47.0
777+13.71	101	101.3	70.0	45.0
780+48.34	163	162.9	70.0	43.0
TOTAL:		407	190	135

MAILBOX TURNOUTS	
LOCATION	AGGREGATE SHOULDERS, TYPE A - 6" (TON)
IL 4 - RIGHT	
777+33 TO 777+83	9.7
779+70 TO 780+20	9.7
TOTAL:	
	19

PAVEMENT PATCHING 12" INCH SCHEDULE				
LOCATION	LENGTH (FT)	LANE WIDTH (FT)	PAVEMENT PATCHING TYPE II (SQ. YD.)	
IL 4 - SB				
773 +	50	6.0	12.0	8.0
778 +	50	6.0	12.0	8.0
778 +	60	6.0	12.0	8.0
779 +	00	6.0	12.0	8.0
779 +	20	6.0	12.0	8.0
779 +	30	6.0	12.0	8.0
779 +	40	6.0	12.0	8.0
779 +	50	6.0	12.0	8.0
779 +	60	6.0	12.0	8.0
780 +	00	6.0	12.0	8.0
780 +	10	6.0	12.0	8.0
780 +	90	6.0	12.0	8.0
781 +	00	6.0	12.0	8.0
781 +	10	6.0	12.0	8.0
781 +	45	10.0	12.0	13.3
782 +	20	6.0	12.0	8.0
783 +	00	6.0	12.0	8.0
SUBTOTAL:				141.3
ANTICIPATED FAILURES (15%):				21.2
TOTAL:				163

TEMPORARY RAMPS			
LOCATION			AREA (SQ YD)
STA	TO	STA	(SQ YD)
IL 4			
768+65	TO	769+15	12
783+00	TO	783+46.5	20
TOTAL:			32

HMA SURFACE REMOVAL BUTT - JOINT			
LOCATION			(SQ YD)
STA	TO	STA	(SQ YD)
IL 4 - RIGHT			
768+65	TO	769+15	78
782+96.5	TO	783+46.5	94
TOTAL:			172

STRIP REFLECTIVE CRACK CONTROL TREATMENT			
LOCATION			STRIP REFLECTIVE CRACK CONTROL TREATMENT (FOOT)
STA	TO	STA	(FOOT)
IL 4 - RIGHT			
769+45	TO	775+31	586.0
775+31	TO	781+14	583.0
781+14	TO	782+96.5	182.5
TOTAL:			1352

PIPE UNDERDRAINS			
LOCATION		PIPE UNDERDRAIN 4" (FOOT)	PIPE UNDERDRAIN REMOVAL (FOOT)
IL 4 - RIGHT			
769+00	TO	775+31	631
775+31	TO	782+96.5	766
TOTAL:		1397	766