

PAVEMENT MARKING SCHEDULE													
LOCATION			TEMPORARY PAVEMENT MARKING				THERMOPLASTIC PAVEMENT MARKING				SHORT-TERM PAVEMENT MARKING (2 LIFTS)	SHORT-TERM PAVEMENT MARKING (2 LIFTS)	WORKZONE PAVEMENT MARKING REMOVAL
			LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)	LINE, 12" SOLID (WHITE)	LETTERS & SYMBOLS (WHITE)	LINE, 4" SOLID (WHITE)	LINE, 4" SOLID (YELLOW)	LINE, 12" SOLID (WHITE)	LETTERS & SYMBOLS (WHITE)			
STA	TO	STA	FOOT	FOOT	FOOT	SO.FT	FOOT	FOOT	FOOT	SO.FT	FOOT	FOOT	SO.FT
IL 4 - RIGHT													
768+65	TO	769+05	40	80				40	80		8	32	4
769+05	TO	775+65	660	2640	144			660	2640	144	108	1056	129
775+65	TO	777+13.92	284	230		31.2		264	230		42	92	15
777+13.92	TO	782+96.5	583	2224	135			583	2224	135	93	358	50
782+96.5	TO	783+46.5	50	100				50	100		8	40	5
SUBTOTAL			1597	5274	279	31		1597	5274	279	255	1576	203
TOTAL			6871		279	31		6871		279	31	1831	203

TEMPORARY EROSION AND SEDIMENT CONTROL					
LOCATION			PERIMETER EROSION BARRIER	TEMP EROSION CONTROL BARRIER	TEMPORARY EROSION CONTROL SEEDING
			(FEET)	(SQ YD)	5 SEEDINGS (POUND)
IL 4 - RIGHT					
768+65	TO	769+36	111	190	20
769+36	TO	774+00	474	2180	225
774+00	TO	777+14	308	1088	112
777+14	TO	780+48	313	1174	121
780+48	TO	783+46.5	308	1029	106
TOTAL			1514	5661	585

RAISED PAVEMENT MARKERS						
LOCATION			RAISED REFLECTOR PAVEMENT MARKER ONE-WAY AMBER	RAISED REFLECTOR PAVEMENT MARKER ONE-WAY CRYSTAL	RAISED REFLECTOR PAVEMENT MARKER TWO-WAY AMBER	RAISED REFLECTOR PAVEMENT MARKER REMOVAL
STA	TO	STA	(EACH)	(EACH)	(EACH)	(EACH)
IL 4 - RIGHT						
768+65	TO	777+13.92	28	3	14	11
777+13.92	TO	783+46.5	29	17	6	8
SUBTOTAL			57	20	20	19
TOTAL				97		19

DITCH CHECK SCHEDULE						
LOCATION			SPACING	LENGTH	QUANTITY	TEMPORARY DITCH CHECK
			(FEET)	(FEET)		(FEET)
IL 4 - RIGHT						
769+60	TO	773+00	100	16	3	54
773+00	TO	774+00	20	33	5	165
774+00	TO	775+00	33	30	3	91
775+00	TO	777+14	50	25	4	107
777+14	TO	778+00	50	24	2	41
778+00	TO	779+00	100	29	1	29
779+00	TO	780+50	33	33	5	150
780+50	TO	781+00	33	21	2	32
781+00	TO	782+00	50	20	2	40
TOTAL						709

EARTHWORK SCHEDULE							
LOCATION			EARTH EXCAVATION	TOTAL EXCAVATION ADJUSTED FOR 25% SHRINKAGE	EMBANKMENT	BALANCE WASTE (+) SHORTAGE (-)	FURNISHED EXCAVATION
STA	TO	STA	(CU YD)	(CU YD)	(CU YD)	(CU YD)	(CU YD)
IL 4 - RIGHT							
769+36	TO	770+00	69	52	526	-475	475
770+00	TO	771+00	57	43	876	-833	833
771+00	TO	772+00	31	24	876	-852	852
772+00	TO	773+00	206	154	717	-563	563
773+00	TO	774+00	391	293	443	-150	150
774+00	TO	775+00	417	313	193	120	-120
775+00	TO	776+00	417	313	69	244	-244
776+00	TO	777+14	333	250	10	240	-240
777+14	TO	778+00	293	220	17	203	-203
778+00	TO	779+00	426	319	22	297	-297
779+00	TO	780+00	420	315	0	315	-315
780+00	TO	781+00	187	140	0	140	-140
781+00	TO	782+00	113	85	0	85	-85
782+00	TO	783+00	124	93	0	93	-93
TOTAL			3484	2613	3747	-1134	1134

SEEDING SCHEDULE							
LOCATION			SEEDING CLASS 2A	NITROGEN FERTILIZER NUTRIENTS	PHOSPHORUS FERTILIZER NUTRIENTS	POTASSIUM FERTILIZER NUTRIENTS	MULCH METHOD 2
STA	TO	STA	(ACRE)	(LB)	(LB)	(LB)	(ACRE)
IL 4 - RIGHT							
768+65	TO	769+36	0.04	4	4	4	0.04
769+36	TO	774+00	0.45	41	41	41	0.45
774+00	TO	777+14	0.22	20	20	20	0.22
777+14	TO	780+48	0.24	22	22	22	0.24
780+48	TO	783+46.5	0.21	19	19	19	0.21
TOTAL			1.17	105	105	105	1.17