

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021 90% FED 10% STATE			CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0021 90% FED 10% STATE				
48100100	AGGREGATE SHOULDERS, TYPE A	TON	119	119			70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	562	562			70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1				
50105220	PIPE CULVERT REMOVAL	FOOT	135	135			70300100	SHORT TERM PAVEMENT MARKING	FOOT	1831	1831				
50800105	REINFORCEMENT BARS	POUND	930	930			70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	31.2	31.2				
54002020	EXPANSION BOLTS 3/4 INCH	EACH	8	8			70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6871	6871				
54003000	CONCRETE BOX CULVERTS	CU YD	6.5	6.5			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	279	279				
54200220	PIPE CULVERTS, CLASS D, TYPE 1 15"	FOOT	190	190			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	203	203				
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	5	5			* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	31.2	31.2				
60107600	PIPE UNDERDRAINS 4"	FOOT	1397	1397			* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	6871	6871				
60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	67	67			* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	279	279				
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	5	5			* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	97	97				
67100100	MOBILIZATION	L SUM	1	1											
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1											

* SPECIALTY ITEM

FILE NAME	USER NAME	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...			314	(110.111)-1	MADISON	34	4
									CONTRACT NO. 76F76	
									ILLINOIS FED. AID PROJECT	