

PAVEMENT MARKING SCHEDULE

LOCATION			THERMOPLASTIC PAVEMENT MARKING -							SHORT TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING				WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT			
			LINE 4"			LINE 12"		LINE 24"	LETTERS AND SYMBOLS		- LINE			LETTERS AND SYMBOLS		MARKER REMOVAL	MARKER		
			SOLID	SKIP-DASH	SOLID	DIAGONAL	CROSS WALK	SOLID			4"	12"	24"						
STA.	TO	STA.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH
631+00.00	TO	636+46.50	1093		1093					173.1	2186						747.9	7	7
BRIDGE OMISSION																			
639+60.50	TO	640+35.50	150		75					20.4	225						77.3	1	1
640+35.50	TO	646+35.50	1200	150	600					163.5	1950						668.2	8	8
646+35.50	TO	646+92.35	113.7	14.3						15.6	128						44.4	1	1
646+92.35	TO	658+00.00	2215.3	277	1107.7					302.1	3600						1233.6	14	14
658+00.00	TO	661+14.84	629.7	78.8						86.1	708.5						245.7	4	4
661+14.84	TO	670+09.80	1790	223.8	895					244.2	2908.8						996.7	11	11
670+09.80	TO	691+35.00	4250.4		4250.4					579.6	8500.8						2898	27	27
691+35.00	TO	700+65.00	1860	232.5	930					253.8	3022.5						1035.7	12	12
700+65.00	TO	702+25.00	320	40						43.8	360						124.9	2	2
702+25.00	TO	706+98.15	946.3	118.3	473.2					129.3	1537.8						527	6	6
706+98.15	TO	707+28.76	61.3		61.2					16.8	122.5						42.7	2	2
707+28.76	TO	710+27.93	598.4		1196.7	104.8				163.2	1795.1	104.8					721.3	14	14
710+27.93	TO	727+57.21	3458.6	864.7	3458.6				280.8	943.8	7781.9		280.8				2979.6	86	86
727+57.21	TO	728+20.21	126		252	35.3				34.8	378	35.3					165.2	7	7
728+20.21	TO	728+94.22	148.1							40.8	148.1						53.9		
728+94.22	TO	729+94.22	300		200				31.2	54.6	500		31.2				203.9	15	15
729+94.22	TO	730+54.22	120		120					33	240						83.7	3	3
730+54.22	TO	869+26.21	27744	6936	27744		82.2	45	2184.8	7566.6	62424	82.2	45	2184.8	24005.7	694	694	694	694
869+26.21	TO	869+91.46	130.5							36	130.5						47.5	4	4
869+91.46	TO	870+80.80	178.7		374.9	79.9				49.2	553.6	79.9					269.9	12	12
870+80.80	TO	871+17.53	73.5							20.4	73.5						26.7		
871+17.53	TO	874+00.00	847.5		564.9	132.8			31.2	231.3	1412.4	132.8	31.2				660.5	24	24
SUBTOTAL			48355	8935.4	43396.6	352.8	82.2												
TOTAL			100687			435	45	2528	11202	100687	435	45	2528	37860	954	954			

EARTHWORK SCHEDULE

LOCATION		EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
STATION	TO STATION	CU YD	CU YD	CU YD	CU YD
IL ROUTE 3					
647+20.00	TO 664+81.00	149.4	112.1	62.1	50.0
TOTAL		149.4	112.1	62.1	50

EROSION CONTROL SCHEDULE

LOCATION		LT OR RT	SEEDING, CLASS 2	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	MULCH, METHOD 2
STATION	TO STATION		ACRE	POUND	POUND	POUND	ACRE
IL 3							
STA 647+20.0	TO STA 664+81.0	LT	0.25	22.5	22.5	22.5	0.25
STA 647+20.0	TO STA 664+81.0	RT	0.25	22.5	22.5	22.5	0.25
TOTAL			0.5	45	45	45	0.5